

4-020129

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-04,216-0000
SE SE SW /4 SEC. 15, 18 S, 11 W
330 feet from S section line
2970 feet from E section line

Operator license# 4767

Lease: Drew B-P Well # 4
County: Barton 107.97

Operator: Ritchie Exploration, Inc.
Address: P.O. Box 783188
Wichita, Kansas 67278-3188

5/16

Well total depth 3322 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 280 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524-0209

Company to plug at: Hour: 2:00 P.M. Day: 16 Month: May Year: 2000

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Ordered out 215 sxs 60/40 pozmix - 10% gel - 400# hulls.
Prod Perfs at 2846' - 2856'; 3032' - 3265'.
Cast iron bridge plug at 2950'.
Shot casing off at 1800'.

Plugging Proposal Received by: Bruce Basye

Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:15 P.M., Day: 16 Month: May, Year: 2000

Actual plugging report: 8 5/8" set at 280' w/150 sxs cement. 5 1/2" set at 3310' w/200 sxs cement. Sanded off to 2800' and topped with 5 sxs cement using a dump bailer.
Shot off casing at 1800'.

Pulled casing to 1380' - tied onto and pumped 125 sxs with 200# hulls.
Pulled casing to 600' - tied onto and spotted 50 sxs with 200# hulls.
Pulled casing to 280' - tied onto and circulated cement with 65 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD

Bottom plug(in place): YES , CALC , NO

Plugged through TUBING , CASING

Anhy.plug: YES NO

Dakota plug: YES , NO

Elevation: 1781 GL

I did / did not observe the plugging.

Jay P. [Signature]
(agent)

INVOICED

DATE 5/19/00

INV. NO. 61758

Form CP-213
R