

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00534-00-00
Spot: CSESWNW Sec/Twnshp/Rge: 30-18S-11W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: ROBL Well Number: 1
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 5363
Operator Name: BEREXCO, INC.
Address: 100 N. BROADWAY, STE. 970
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 244
Production: Size 5.5 feet: 3459 *112.45*
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 9/19/00 1:30:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
CIBP @ 3330' and 3155'. FL. 75'.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/19/2000 4:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 244' w/145 sxs. 5 1/2" set at 3459' w/100 sxs.
Perforated casing at 1450' & 675'.
Ran tubing to 3000' - tied onto and pumped 70 sxs w/200# hulls.
Pulled tubing to 2000' - tied onto and pumped 90 sxs w/200# hulls.
Pulled tubing to 700' - tied onto and circulated cement up 5 1/2" w/50 sxs w/200# hulls. Pulled tubing out of the hole.
Tied onto 5 1/2" and circulated cement up 8 5/8".
Shut 8 5/8" in and pumped to pressure.
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
STATE CORPORATION COMMISSION
9-22-2000
SEP 22 2000

Remarks: THIS LEASE WAS RENAMED BAILEY 1-1. ALLIED CEMENTING COMPANY.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: TBG

District: 04

Signed *Jay Pfeifer*

(TECHNICIAN)

INVOICED

DATE 9/25/00

INV. NO. 2001060736

Form CP-2/3

SEP 20 2000


Renamed Bailey 1-1 30-18-11W 53
 THUNDERBIRD DRUG #1 ROBI SE SW NW

Contr. THUNDERBIRD DRUG BARTON County

E. 1813RB Comm. 3-23-57 Comp. 6-28-57 IP 214 BOPD/KC
 PHY POT

Tops	Depth	Datum
HEEB	2968	-1155
BR LM	3080	-1267
LANS	3096	-1283
<i>Arch</i>	<i>1061</i>	<i>+1152</i>
ARB	3383	-1570
TD	3460	-1647

Casing
 8" 244 w 145 S
 5" 3459 100 S
 DST 3080-3126/1 HR, 120' SL 0 & GCM,
 BHP 635#
 DST 3138-70/1 HR, 6/8", 1540' FR 0, 800'
 GSY 0, BHP 1070#
 DST 3229-45/1 HR, 6/7", 1680' FR 0, BHP
 1116#
 DST 3385-93/40", 15' M, BHP 922#
 PERF 3400-02, 3405-08: 4 GOPH: ACID 500
 WTR: SQZ: REPERF 8/3400-02: 12/3405-08
 ACID 500: SWB 11 BWP &
 1/2 BOPH: PLUG 3289: 20/
 3270-75: 1 GOPH, NATL
 ACID 750: FLO 13 BOPH



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS