

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CR-1
Rev. 03/92

15.081-00099-0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # Completed 7-26-55 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Helmerich & Payne, Inc. KCC LICENSE # 5293 ^{6/95}
(owner/company name) (operator's)

ADDRESS P.O. Box 558 CITY Garden City

STATE Kansas ZIP CODE 67846 CONTACT PHONE # (316) 276-3693

LEASE Black WELL# 1 SEC. 19 T. 27 R. 31 (East/West)

C NW SPOT LOCATION/QQQQ COUNTY Haskell

1320 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 508 CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 2714 CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs 2664'-74' and 2684'-94'

ELEVATION 2843 DF T.D. 2715 PBTD 2703 ANHYDRITE DEPTH 1790
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU pulling unit. RTH with string shot and backoff 1 1/2 tubing @ + 2000'. TOOH with 1 1/2" tubing. TTH with 2 3/8"x4 1/2" retainer on 2 3/8" tubing Set retainer @ + 1200'. RU cementers. Squeeze off Glorietta casing leak with 100' s/s
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Jehlik PHONE# (316) 276-3693

ADDRESS P.O. Box 558 City/State Garden City ZIP 67846

PLUGGING CONTRACTOR Halliburton (company name) 1-10-95 LICENSE # 5293

ADDRESS 525 Central Park Dr. Ste 210 PHONE # 405-525-3344

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) OKC 73105

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-3-95 AUTHORIZED OPERATOR/AGENT: Arthur L. Childers
(signature)

RECEIVED
STATE CORPORATION COMMISSION
JAN 06 1995
CONSERVATION DIVISION
WICHITA, KANSAS

65/35 Poz "C" with 6% gel. Sting out of retainer. Reverse excess cement. TOOH
with 2 3/8" tubing. PERFORATE Cheyenne @+ 1050'. Establish injection down 4 1/2"
casing. Mix and pump 130 s*~~s~~. 65/35 poz "C" with 6% gel. If well doesn't circulate
pump 175 s*~~s~~. 65/35 Poz "C" with 6% gel down 8 5/8"x4 1/2" annulus. Cut off casing 5' below
ground level. Reclaim location. Per directions of Steve Durant KCC Dodge City Office.



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 10, 1995

Helmerich & Payne Inc
P O Box 558
Garden City KS 67846

Black #1
API 15-N/A
1320 FNL 1320 FWL
Sec. 19-27S-31W
Haskell County

Dear Ken Jehlik,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760