

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 24 2000

4-24-2000

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

CONSERVATION DIVISION  
WICHITA, KS

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-20,613-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056  
(owner/company name) (operator's)

ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE Breitenbach "B" WELL# 1-30 SEC. 30 T. 24S R. 16W (East/West)

1180' - ENL 440' FEL-NE/4 SPOT LOCATION/QQQQ COUNTY Edwards

4230' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

430' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 251 CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4439' CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4338'-4344'

ELEVATION 2086/2095' T.D. 4440 PBT D 4409' ANHYDRITE DEPTH 1102'-1113'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy mud, Hulls, Cement and Halliburton plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob long

PHONE# (316) 793-0915

ADDRESS P.O. Box 158 City/State Belpre, Kansa 67519

PLUGGING CONTRACTOR Quality Well Service, Inc. KCC LICENSE # 31925

ADDRESS 249 Beth Drive Sterling, KS. 67579 (company name) (contractor's)  
PHONE # ( X316 ) 278-2476

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 04/20/2000 AUTHORIZED OPERATOR/AGENT: Frank Greenbaum  
(signature)

Frank Greenbaum

6/00

117 -  
12

8/00

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 24 2000

CONSERVATION DIVISION  
WICHITA, KS

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- G. BREITENBACH "B" #1-30  
Located: 1050' FNL; 430' FEL, NE/4, Section 30-24S-16W,  
Edwards County, Kansas

OWNER: F. G. Holl, et al.  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 3, 1980  
COMPLETED: January 9, 1980

TOTAL DEPTH: 4440'

LOG

0 - 90 Surface Soil and Sand  
90 - 254 Shale  
254 - 1102 Shale and Sand  
1102 - 1113 Anhydrite  
1113 - 2135 Shale  
2135 - 4290 Lime and Shale  
4290 - 4318 Miss. Chert  
4318 - 4440 Shale, Sand, Lime and  
Chert

CASING RECORD

Ran 7 joints 8 5/8" casing, 239.03' set  
at 251' K.B. with 200 sacks 60/40 Pozmix  
with 3% cc. Plug down at 3:00 PM, 1-3-80,  
by Howco.  
  
Ran 126 joints 4 1/2", 10.5# casing.  
4430.14' pipe set at 4439' K.B. Cemented  
with 175 sacks 50/50 Pozmix with 2% gel,  
18% salt, 5# gilsonite per sack, 3/4 of  
1% CFR-2 and 50' rotating scratchers.  
Plug down at 11:15 AM, 1-9-80, by Howco.

Deviation Surverys: 1° at 2211'  
1 3/4° at 4440'



---

## Kansas Corporation Commission

---

Bill Graves, Governor   John Wine, Chair   Cynthia L. Claus, Commissioner   Brian J. Moline, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.  
6427 East Kellogg  
Wichita, KS 67207

April 27, 2000

BREITENBACH G - B #1-30  
API 15-047-20613-00-00  
1050 N 430 E  
E2E2NE 30-24S-16W  
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-8888