

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

3-20-2000

FORM RECEIVED
KANSAS CORP COMM

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21,092 - 00-00 (Identifier number of this well). This must be stated for wells drilled since 1967; if no API# was issued, indicate spud or completion date. ^{2000 MAR 20} _{1/00}

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS 6427 E, Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 6727-0167 CONTACT PHONE # (316) 684-8481

LEASE BRENSING 'C' WELL# 3-1 SEC. 1 T. 24S R. 17 (East/West)

- SW - SE - SE SPOT LOCATION/OQQO COUNTY Edwards

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 255' CEMENTED WITH 210 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4385' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 4330'-4334', 4259'-4290' OA, CIBP @ 4320'

ELEVATION 2095 KB T.D. 4390' PBTD NA ANHYDRITE DEPTH 1101'-1120'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy mud, hulls, cement and plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# () (316) 995-3171 Office (316) 793-0915 Cell Phone

ADDRESS P. O. Box 158 City/State Belpre, Kansas 67519

PLUGGING CONTRACTOR Quality Well Service, Inc. KCC LICENSE # 31925

ADDRESS 249 Beth Drive Sterling, Kansas 67579 PHONE # (316) 278-2476
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-17-00 AUTHORIZED OPERATOR/AGENT: W. Bruce Billman
(signature)

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

RECEIVED
KANSAS CORP COMM

2000 MAR 20 P 1:03

WELL LOG ----- BRENSING "C" #3-1
Located: SW SE SE, Section 1-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 8, 1983

COMPLETED: March 14, 1983

TOTAL DEPTH: 4390'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 110 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# new casing. 241.59' pipe set at 255' K.B.
110 - 257 Clay and Shale	Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 2:45 PM, 3-8-83, by Howco.
257 - 1106 Shale, Sand, Red Bed	
1106 - 1125 Anyhdrite	
1125 - 1210 Shale	
1210 - 2080 Shale and Lime Stringers	
2080 - 4390 Lime and Shale	Ran 13 joints 4 1/2", 10.5# used casing and 98 joints 4 1/2", 10.5# new casing. 4373.03' pipe set at 4385' K.B. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix, plus our regular additives. Plugged rat hole and water well with Lite cement. Plug down at 5:05 AM, 3-14-83, by Howco.

Deviation Surveys: 3/4° at 2239'
1° at 4305'



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

March 23, 2000

BRENSING C #3-1
API 15-047-21092-00-00
330 S 990 E
SW SE SE 1-24S-17W
EDWARDS COUNTY

Dear Rob Long:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor