

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-069-20,206-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Rine Exploration Company OPERATORS LICENSE NO. 5020

ADDRESS Suite #645, 300 W. Douglas, Wichita, KS 67202 PHONE # (316) 262-5418

LEASE (FARM) Ingalls WELL NO. 1-5 WELL LOCATION SE 1/4 NW 1/4 COUNTY Gray

SEC. 5 TWP. 27S RGE. 29W (~~E 1/4 NW 1/4~~) TOTAL DEPTH 5200 Ft. PLUG BACK TD N/A

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 526' CEMENTED WITH 250 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 1860'-50 sacks; 2nd plug @ 870' -
40 sacks; 3rd plug @ 540'-50 sacks; 4th plug @ 40' to solid bridge-10 sacks; rathole-15 sacks;
mousehole-10 sacks; 60-40 poz mix, 6% gel, 2% cc.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No. IS ACO-1 FILED? No.
(If not, explain) "Operator will be completing."

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 6:00 p.m. May 22, 1987

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Noreuil PHONE # (405) 256-8763

ADDRESS P. O. Box 1226, Woodward, OK 73802

PLUGGING CONTRACTOR Rine Drilling Company LICENSE NO. 5654

ADDRESS Suite #600, 300 W. Douglas, Wichita, KS 67202 PHONE # (316) 267-1333

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. Bradford Rine
(Operator or Agent) (M. Bradford Rine)

DATE: June 3, 1987
Wichita, Kansas 6-8-1987