

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KANSAS

MAR 17 1993

3-17-1993

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-151-21830-A (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050 *4/93*
(owner/company name) (operator's)

ADDRESS P.O. Box 347 CITY Chase

STATE Kansas ZIP CODE 67524 CONTACT PHONE # (316) 938-2943

LEASE Bryant (OWWO) WELL# A-1 SEC. 31 T. 27 R. 15W (East/West)

C - SE - SE SPOT LOCATION/QQQQ COUNTY Pratt

 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 402' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4730' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4614-32' & 4591-95'

ELEVATION 2080 G.L. T.D. 4760' PSTD ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING We will plug well according to the rules and regulations of the State of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Kelso Casing Pulling, Inc. PHONE# (316) 938-2943

ADDRESS P.O. Box 347 City/State Chase, KS 67524

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050 *4/93*
(company name) (contractor's)

ADDRESS P.O. Box 347 Chase, KS 67524-0347 PHONE # (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/16/93 AUTHORIZED OPERATOR/AGENT: *R. David Kelso*
(signature)

4450 Cen Top

**A & A DISCOVERY
HILL CITY KS 67642**

**31-27 -15W
C SE SE**

#A-1 BRYANT QWVO

site: 3/4 N & 4-1/2 W OF CULLISON KS
 contr: DUKE DRILLING #1
 geol: SCOTT ALBERG

city: PRATT
 acid: WELLSFORD EXT (1/4 E)

API 15-151-21830-A

if date 10/30/90 spd date 11/13/90 drig comp 11/15/90 card issued 02/25/91 last revised 02/25/91

ELV: 2085 KB, 2080 GL LOG	
tops.....	depth/datum
BR LM.....	4091 -2006
LANS.....	4114 -2029
BKC.....	4449 -2364
CHER SH.....	4580 -2495
CHER SD.....	4592 -2507
MISS.....	4612 -2527
KIND CHT.....	4654 -2569
KIND SH.....	4672 -2587
VIOLA.....	4732 -2647
RTD OLD.....	4794 -2709

IP status:
 OIL, P 4 BO & 20 BWPD, CHER 4591-4595, MISS 4614-4632
 OLD INFO: OPERATOR WAS MARMAC PETROLEUM CO, 1-31 BRYANT, SPD 04/27/87, 05/05/87 8-5/8" 402 / 250 SX, D&A, VIOLA, 05/05/87 (CARD ISSUED 05/27/87)
 CONTR: DUKE DRILLING
 GEOL: DOUG MCGINNESS II
 NO CORES
 DST (1) 4567-4630 (CHER, MISS), / 30-45-60-90, GTS / 6", GA 90 MCFGPD DECR TO 14 MCFG / 90" & STAB, REG 270' MDY OIL ISIP 1055# IFP 71# -71# FFP 82# -82#

A & A DISCOVERY
HILL CITY KS 67642

31-27 -15W
C SE SE

#A-1 BRYANT QVWQ

DST (2) 4592-4630 (CHER, MISS), / 30-45-60-90, (2ND OP) GTS / 2", TSTM, REC 60' GCM, W / SPKS OIL, 60' OIL & GCM ISIP 1032# FSIP 892# IFF 94# -94# FFP 106# -106# BHT 122 *

NEW INFO: FR 10/30/90 , RE-ENTERED 11/13/90 WSH DWN TO 4760 DC 11/15/90 CSG: SET 4-1/2" 4730 / 100 SX TRGT ZN: MISS, PTD 4700 (MOLA), MICT - CO, PF (MISS) 4614-4632 & (CHER SD) 4591-4595, W / 2 SPF, AC 1000 GAL (15%), ZNS TRTD TOGETHER, FRAC 46,000# SD & 1000 BBL GEL WTR AT 22 BPM, SO, SET 2-3/8" TBG AT 4855, NO PKR, POP; P 4 BO & 20 BWPD (GR 31) 12/13/90, COMMINGLED

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 17, 1993

Kelso Casing Pulling, Inc.
P.O. Box 347
Chase, KS 67524

Bryant (OWWO) A-1
API 15-151-21830
C Se Se
Sec. 31-27-15W
Pratt County

Dear Sirs,


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W McArtor
Dodge City, KS 67801
(316)-225-6760