

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County, Sec. 30 Twp. 27 Rge. 13 (E) (W)

Location as "NE/CNWxSWx" or footage from lines. NW NW NE
Lease Owner: Shallow Water Refining Company
Lease Name: Apt. #1 Well No. _____
Office Address: Kansas City, Missouri 64112
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/16/68 _____ 19____
Plugging completed 12/28/68 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4140 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	400'	none
				5 1/2"	4140	2982'

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 4030', dumped 5 sacks of cement with 3" bailer. Loaded hole, shot pipe at 3219', 3125', worked pipe at no gain. Pumped 40 barrels oil, chased plug to 3019', let pipe set. Shot pipe at 3001', worked pipe at no gain. Pumped 40 barrels oil, chased plug to 2900', worked pipe loose and pulled 90 joints. Bailed hole to 200', set 10' rock bridge and dumped 25 sacks of cement. Mudded to 40', 10' rock bridge and capped with 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of January 19 69

My commission expires February 15, 1971

Margaret Melcher
Notary Public.



D R I L L E R S L O G

Operator: W. J. Coppinger
 320 Union Natl Bk Bldg., Wichita
 Contractor: Coppinger Drilling, Inc.

Re: Apt #1
 NW NW NE Sec. 30-27S-13W
 Pratt County, Kansas

Clay and Sand	50'
Sand	90
Red Bed Sand	360
Shale	400
Red Bed and Sand	840
Sand, Red Bed & Shale	1300
Shale	1520
Shale and Salt	1665
Shale	1780
Broken Lime	1820
Shale	1840
Lime	1845
Lime, Shale & Shells	1915
Lime and Shale	2025
Shale & Broken lime	2120
Lime and shale	2225
Lime	2275
Sandy lime	2315
Broken Lime	2390
Lime and shale	2465
Shale & broken lime	2555
Lime & Shale	3355
Lime	3520
Lime and shale	3570
Lime	3617
Lime and shale	3737
Shale	3800
Lime and shale	3830
Lime	3880
Lime and shale	3920
Lime	4174
Shale and lime	4270
Chert and lime	4300
Lime and shale	4320
Shale	4326
Lime	4364
Chert & junk	4383
Lime	4396
Chert and lime	4420
Sand and chert	4430
Lime and chert	4442
Lime and shale	4455

Casing Record:

8-5/8" set at 400' with 250 sax posmix cement.
 5-1/2" set at 4140 with 150 sax regular cement.

TOPS:

Heebner	3669
Brown Lime	3820
Lansing	3840
Conglomerate	4266
Mississippi	4273
Kinderhook	4299
Viola	4326
Simpson Shale	4409
Simpson Sand	4415
Rotary TD	4455

Commenced: July 1, 1953
 Completed: July 23, 1953
 Elevation: 1933 R.B.
 1928 Ground

Rotary Total Depth 4455

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss.

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true record and log of the well drilled at the location above described.

Subscribed and sworn to before me this 28th day of July 1953.

My commission expires: March 7, 1956

W. J. Coppinger

Wesley Broadbent

 Notary Public

*cc: well log Bureau
 7-28-53*

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 5 1968
 CONSERVATION DIVISION
 Wichita, Kansas

file