

WICHITA SEP 15 1970


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pratt County, Sec. 30 Twp. 27 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW NE
Lease Owner Maurice L. Brown
Lease Name Apt #2 Well No.
Office Address Kansas City, Missouri 64141
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/1/70 19
Plugging completed 9/4/70 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4145 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	402	none
				5 1/2"	4180	3220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4145', sanded to 3800' and dumped 5 sacks of cement. Shot pipe at 3247', 3215', worked pipe loose and pulled 100 joints. Set rock bridge at 365', dumped 5 sacks of cement. Bailed fluid down to top of plug, called ready mix out and dumped 5 yards.

PLUGGING COMPLETE.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 8th day of September, 1970

My commission expires 2/15/71

Margaret Mulcher Notary Public.

DRILLERS LOG

Operator and Contractor: W. J. Coppinger
320 Union National Bank Bldg.
Wichita, Kansas

Re: Apt #2
NW SW NE
Section 30-27s-13w
Pratt County, Kansas

Elevation: 1928 R.B.

Commenced: May 24, 1955
Completed: June 10, 1955

Casing Record:
8-5/8" set at 402' with 250 sack pozmix
5-1/2" set at 4180' with 150 sack cement

Tops: (Electric log tops)

Sand and gravel	140
Clay	175
Shale and red bed	402
Red bed & shells	822
Anhydrite	855
Shale and shells	1830
Lime and shale	3420
Lime	3450
Lime and shale	3815
Lime	3915
Lime and shale	3975
Lime	4060
Lime and shale	4080
Lime	4125
Lime and shals	4210
Lime and shale and chert	4230
Cherty lime and shale	4250
Cherty lime	4310
Shale	4333
Chert	4347

Heebner	3657
Brown Lime	3810
Lansing-Kansas City	3828
Base Kansas City	4160
Conglomerate	4238
Mississippian	4248
Kinderhook	4310
Viola	4330
R T D	4347

Rotary Total Depth: 4347'
Plug back T.D. 4145'

STATE OF KANSAS
COUNTY OF SEDGWICK, SS.

I hereby certify that the above information is true and correct to the best of my knowledged.

Lee Poulsen
Lee Poulsen

Subscribed and sworn to before me this 13th day of June, 1955.

Mayce Broadus
Mayce Broadus, Notary Public

My commission expires: March 7, 1956



RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1970
CONSERVATION DIVISION
Wichita, Kansas