

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

County Sec 30 Twp 27S Rge 13 (E) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines Approx. 024 011 010  
Lease Owner J.H. Huber Corporation et al.  
Lease Name Shanley Well No. 1  
Office Address Drawer 831, Dargen, Texas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 1-31-1946  
Application for plugging filed 3-11-1946  
Application for plugging approved 3-11-1946  
Plugging commenced 3-11-1946  
Plugging completed 3-11-1946  
Reason for abandonment of well or producing formation Dry

NORTH


Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well H.W. Korr.  
Producing formation Depth to top Bottom Total Depth of Well 4595 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	402'	
				8 3/4"	4535'	2631'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud Hole to 200', run 15 cu cement.  
Mud Hole to 25', run 10 cu cement to  
base of collar.

PLUGGING  
FILE SEC 30 27 R 13 W  
BOOK PAGE 46 LINE 45

APR 16 1946  
9-16-46

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J.H. Huber Corporation.  
Address Drawer 831, Dargen, Texas.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Edward A. Huffman (employee of owner) or (owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edward A. Huffman  
Edward A. Huffman J.H. Huber Corporation,  
308 Petroleum Building, Wichita, Kansas.

Subscribed and Sworn to before me this 10th day of April, 1946

My commission expires February 2, 1949

E. Jeanne Cochran  
Notary Public.

Farm Name: Shanley No. 1  
 Company: J.M. Huber Corporation et al.  
 Commenced: 12-9-45  
 Completed: 1-31-46  
 Total Depth: 4585

Location: Approx. C8 1/2 NW NE  
 530' fr EL 990' fr EL MEA  
 Sec. 30-27E-13W.  
 Pratt county, Kansas.  
 Production: Dry and Abd.

Drilled with Rotary and Cable.

Elevation: 1938

CASING USED: 10" 402' 175 ex.  
 5" 4535' 125 ex.

Formation	Depth	Notes
shale and sand	131	
shale, shells and red bed	325	
red bed	402	
red bed, shale and shells	870	
shale and shells	1275	
shale and shells, salt	1605	
lime and shale	1650	
shale, shells & lime	1850	
lime and shale	2520	
lime	2560	
lime and shale	3125	
lime	3180	
lime and shale	3215	
lime, shale and broken lime	3315	
lime and broken lime	3415	
lime and shale	3855	
lime	3890	
lime and shale	3960	
lime	4195	
lime and shale	4215	
lime	4280	
chert	4314	
shale	4343	
cherty lime	4369	
cherty lime & shale	4404	
cherty lime & chert	4425	
chert	4429	
sand	4461	
sand and shale	4488	
shy shale and shale	4520	
sand and shale	4534	
lime	4585	
Total Depth.		

  

Formation	Depth	Notes
Popoka	3343	
Heobner	3618	
Toronto	3633	
Douglas	3657	
Brown lime	3838	
Lansing	3853	
Soft Drlg.	3946-51	all porosity, no show.
	3970-3975	correction applied by strapping drill pipe at 3890
Soft Drlg.	3977-84	
HDST	4007-19	open 30 min. rec. 30' mud, trace of oil cut mud.
Soft Drlg.	4023-29	little por. trace dark spotted stain.
Porous	4054-59	trace stain, very faint odor.
Soft Drlg.	4085-4100	light odor, with light uniform stain.
Mississippi chert	4274	
shale	4314	
Viola	4343	
Simpson	4429	
Cored	4440-50	recovered 7'
	1'	shaly dolomite, no porosity.
	6'	sand, med to good porosity, oil saturated.
HDST	4438-50	open 30 min. recovered 1400' salt str. no oil.
sand	4468	
	4471-75	finely xln dolomite, some dark brown coloration.
Arbuckle	4534	
Rotary Total Depth	4536	

Rigged up standard tools. Loaded hole with 1400' water. Drilled the plug and drilled deeper 4540. Unloaded the hole and had no shows, oil or water. 800' water in 2 hours at 4582-85 TD. Dumped 6 ex cement. Plugged back with cement and cal seal 4430. Ran Gamma Ray log. Perf. Lansing 24/4086-94, small show free oil. 500 acid, 1400' to 700'. Swabbing 1 BO, plus 6 BWPH/30 hours. Fluid declined to 3 1/2 BWPH, 50% oil, 2000 acid (vacuum) swabbed load off. Swabbed 10 BO and 67 BW in 8 hours. Lane Wells plug 4072. Perf. 12/4052-56. 600' fluid in hole 10 minutes. Swabbed 65 BF 4 hours with acid oil. The last hour swab 3 BO and 22 BW. 4000 acid (vacuum) Swabbed down and swabbed estimated 1 BO and 10 BWPH. Swabbed 26 BO, 176BW 30 hours. Set drillable retainer at 4024, squeezed with 100 ex. Maximum pressure 1400#. Perf. 24/4006-14; 12/4002-06; 12/4011-15, no shows. Perf. 24/3875-83, tested 10 GWPH. Perf. 24/3886-94, no increase. 500 acid, swabbed down and swabbed 10 BWPH. Dry and Abandoned.

30 27 13W  
 46 45

APR 16 1946

STATE OF KANSAS )  
 ) ss  
COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log of the Shanley No. 1 located in approximately Center South Half Northeast Quarter of the Northeast Quarter (CS 1/2 NE NE) of Section 30, Township 27 South, Range 13 West, Pratt County, Kansas.

Edward A. Huffman  
Edward A. Huffman  
District Manager.  
J.M. Huber Corporation.

Subscribed and sworn to before me this 18th day of February 1946.

E. Jeanne Castleberry  
Notary Public.

My Commission expires February 2, 1948.

30 27 13W  
46 45