


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 30 Twp. 27S Rge. 13 ~~14~~ (W)
Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner American Petroleum Company of Texas
Lease Name Fitzsimmons Well No. 2
Office Address Box 209 - Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 29 1953
Application for plugging filed November 20 1958
Application for plugging approved November 21 1958
Plugging commenced November 30 1958
Plugging completed December 17 1958
Reason for abandonment of well or producing formation Insufficient Production

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production November 15 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? W. L. LaCamp - Stafford, Kansas. - Yes.-

Name of Conservation Agent who supervised plugging of this well "
Producing formation Lansing K. D. Depth to top 3826 Bottom --- Total Depth of Well 4365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	374'	none 0
				5 1/2"	4365	2684.90

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 4365'
Run 5 sacks of cement at 4365'
Mudded to 300'
Set rock bridge to 285'.
Run 20 sacks of cement at 285'.
Mudded to 30'
Run 10 sacks of cement to cap.

RECEIVED
STATE CORPORATION COMMISSION
12-29-58
DEC 29 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C. E. Shull Casing Pulling Company
Address Box 558 - Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
LEVI B. SHERMAN (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman
Box 209 - Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21th day of December, 1958

Carol J. Bennett
Notary Public.

My commission expires 10-2-60

PLUGGING
FILE SEC 30 T 27 R 13W
BOOK PAGE 146 LINE 45

DRILLERS LOG

COPY

W. J. Coppinger et al

FITZSIMMONS #2
NW SE NW Sec. 30-27S-13W
Pratt County, Kansas

Clay and Sand	165
Red Bed and Shale	374
Red Bed	460
Sandy red bed	625
Red bed	817
Anhydrite	845
Shale and shells	1600
Shale and lime	1830
Lime	1925
Lime and shale	2040
Lime	2100
Lime and shale	2265
Lime	2350
Lime and shale	3285
Lime and sand	3400
Lime	3547
Lime and shale	3755
Shale	3807
Brown Lime	3823
Kansas City Lime	3850
Lime	4151
Lime and shale	4253
Lime	4271
Chert	4288
Shale	4306
Chert	4325
Lime and chert	4355
Cherty lime	4396
Shale	4402
Dolomite & Shale	4426
Lime and shale	4432
Total depth	4432

Casing record:

8-5/8" @ 374 w/250 sax posmix
5-1/2" @ 4370 w/100 sx posmix

Tops:

T Anhydrite	817
T Heebner	3654
T Brown Lime	3807
T Lansing-K.C.	3826
T. Mississippi	4260
T. Kinderhook	4288
T Viola	4306
T. Simpson	4396
Total depth:	4432
Comm:	3-8-53
Comp:	3-29-53
Elevation:	1916 DF
	1919 RB

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss.

I. W. J. Coppinger, being duly sworn on oath, state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

Subscribed and sworn to before me this 30th day of March, 1953.

Notary Public

NOTARY PUBLIC
Commission Expires March 1958
Wichita, Kansas

PLUGGING
FILE SEC 30 T 27 R 13W
BOOK PAGE 146 LINE 45