

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 30 Twp. 27 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Shallow Water Refining Company
Lease Name Apt Well No. 3
Office Address Kansas City, Missouri
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/28/69 _____ 19____
Plugging completed 3/6/69 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4107 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	391	none
				5 1/2"	4132	2772'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded back to 4050', ran 5 sacks of cement. Loaded hole, checked hole, shot pipe at 3205', 3242', pumped 60 barrels oil, chased oil with plug and 80 barrels water, checked hole, plug stopped at 2440', pumped one load water, shot pipe at 3149', 3055', 2957', 2862', 2766', worked pipe loose and pulled 87 joints of 5 1/2" casing. Bailed hole to 230', 10' rock bridge and ran 25 sacks of cement. Mudded hole to 30' and ran 10 sacks of cement. Talled pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1969
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of March, 19 69
Margaret Melcher Notary Public.
My commission expires Feb. 15, 1971



D R I L L E R S L O G

W. J. Coppinger - Apt #3
100' West of SE NW NE
Section 30-27s-13w
Pratt County, Kansas

Casing Record:

Elevation: 1940' R.B.
1937' D.F.

8-5/8" set at 391' with 250 sack
5-1/2" set at 4132' with 150 sack

Commenced: June 21, 1955
Completed: July 4, 1955

Tops:

Sand, gravel & clay	210
Red bed	391
Red bed and shells	836
Anhydrite	870
Shale and shells	1845
Lime	1955
Lime and shale	2530
Shale	2545
Shale and lime	3830
Lime	4132'
R T D	4132

Anhydrite	836'
Heebner	3677'
Brown Lime	3828
Lansing	3848
R T D	4132

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I hereby certify that the above information is true and
correct to the best of my knowledge.

Lee Poulsen
Lee Poulsen

Subscribed and sworn to before me this 6th day of July 1955.

Mayree Broadbent
Mayree Broadbent, Notary Public

My commission expires:

March 7, 1956

