


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Pratt County. Sec. 25 Twp. 27S Rge. 13 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner C. R. A., & Rex & Morris, Inc.  
Lease Name Mc Guire E Well No. 1  
Office Address Box 334, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Feb. 2 1959  
Application for plugging filed " 19"  
Application for plugging approved " 19"  
Plugging commenced " 19"  
Plugging completed " 19"  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4380 Feet  
Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	363	8 5/8"	363	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud from 4380' to 240': Cemented with 20 Sacks cement on Bridge  
Plug @ 240': Filled with mud to 35' and cemented with 10 Sacks of cement on  
Bridge Plug @ 35': Filled to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 7 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rex & Morris Drilling Company  
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure  
Box 334, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1959

My commission expires August 8, 1962  
Elizabeth Deschner Notary Public.

PLUGGING  
FILE SEC 25 T. 27 R. 13 W  
BOOK PAGE 17 LINE 8

Elevation: 1903 R.B.  
1900 D.F.

MC GUIRE "E" # 1

Cooperative Refinery Association  
and  
Rex & Morris Drilling Company

Total Depth: 4380  
Contractor: Rex & Morris Drilling Co.  
Commenced: 1-18-59  
Completed: 2-2-59  
Initial Prod.: D. & A.

Location: NE SE NW  
Section 25-27S-13W  
Pratt County, Kansas

Casing Record:  
8 5/8 @ 363' w/ 250 sacks

FORMATION	DEPTH
Surface Hole	363
Shale, Red beds and Shells	1250
Shale and Shells	1500
Shale and Lime	1830
Lime and Shale	2775
Shale and Lime	2925
Lime and Shale	3284
Shale and Lime	3425
Lime	3482
Shale	3530
Shale and Lime	3794
Lime	4225
Lime and Shale	4272
Lime	4324
Lime	4337
Shale	4342
Dolomite	4347
Shale	4350
Dolomite	4357
Lime	4362
Shale	4367
Sand	4378
Quartzite	4380

Core #1  
" "  
" "  
" #2  
" "  
" "  
" "

T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 7 1959  
CONSERVATION DIVISION

PLUGGING  
FILE SEC 25 T 27 R 13W  
BOOK PAGE 17 LINE 8

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

REX & MORRIS DRILLING COMPANY

By Paul D. Koontz  
Paul D. Koontz, Geologist

STATE OF KANSAS  
COUNTY OF BUTLER, SS.

SUBSCRIBED AND SWORN to before me, a Notary Public, this 6th day of February, 1959.

Elizabeth Deschner  
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962.