

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt

County, Sec. 25 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNW*SW*" or footage from lines SW SW NW

Lease Owner Aylward Drilling Company

Lease Name McGuire Well No. 1

Office Address 813 1st National Bank Bldg. - Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed March 13, 19 61

Application for plugging filed March 12 19 61

Application for plugging approved March 12 19 61


Plugging commenced March 13 19 61

Plugging completed March 13 19 61

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 240', plug at 240' with 15 sacks cement

Mud to 35', plug at 35' with 10 sacks cement

Bridged rat hole and 2 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company

Address _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Paul W. Hesse (employee of owner) ~~or owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 61

Duane Jessup
DUANE JESSUP

Notary Public.

My commission expires December 11, 1961



McGUIRE NO. 1

Casing Record:
8 5/8" - 275'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Location: SW SW NW
Sec. 25-27-13W
Pratt County, Kansas

Commenced: March 13, 1961
Completed: March 24, 1961

Elevation: 1897 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	120	Set 8 5/8" surface pipe at 275' w/225 sacks cement.
Red Bed & Shale	120	140	
Shale, Lime & Red Bed Str.	140	275	
Shale	275	1750	Geological Tops:
Lime & Shale	1750	2365	Heebner 3587
Shale & Shells	2365	2545	Toronto 3600
Shale & Lime	2545	2825	Douglas 3626
Shale	2825	3025	Brown Lime 3765
Shale & Lime	3025	3270	Lansing 3783
Shale	3270	3425	Base Kan. City 4126
Shale & Lime	3425	3562	Mississippian 4213
Sand, Shale & Lime	3562	3690	Viola 4252
Shale	3690	3826	Simpson 4329
Lime	3826	4327	Simpson Dolomite 4334
Lime & Shale	4327	4341	Simpson Sandstone 4358
Lime	4341	4347	
Lime & Shale	4347	4376	
Lime	4376	4379 T.D.	D.S.T. 4016-43 Open 1 hr. Rec. 2790' SW IBHP 1540#/20" - FBHP 1520#/30" FP. 690# - 1410#
			DST 4320-47 Open 1 hr. Rec. 1090' SW IBHP 1330#/20" - FBHP 1295#/30" FP. 125#-550#
			DST 4355-79 Open 1 hr. Rec. 55' VS10CWtyM & 30' VS10CMdyW IBHP 155#/20" - FBHP 110#/30" FP. 60#-75#

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1961

CONSERVATION DIVISION
Wichita, Kansas

D & A

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 29th day of March, 1961

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1961