

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

RECEIVED
2-6-2003
06 2003

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-00126-0000
LEASE NAME Luders A
WELL NUMBER 1

NOTICE: TYPE OR PRINT
Fill out completely and return
to Cons. Div. office within 30 days.

330' Ft. from ~~SE~~ ^{SW} Line of Section (circle one)
2310' Ft. from ~~SE~~ ^{SW} Line of Section (circle one)

LEASE OPERATOR Martin Oil Producers, Inc.
ADDRESS 150 N. Main #1010
CITY, STATE, ZIP Wichita, KS 67202
PHONE#(316)264-0352 OPERATORS LICENSE NO. 5097
Charater of Well gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION NE NE NW
SEC. 13 TWP. 27 S. RGE 13 XX or (U)
COUNTY Pratt
Date Well Completed 8-7-53
Date Plugging Commenced 12-11-02
Date Plugging Completed 12-16-02

The plugging proposal was approved on 10-3-02 (date)
by Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? _____

Producing Formation(s) 4310'-15', 4301'-04', 4292'-4301' Depth to Top 4412' Bottom 4376' T.D. 4412'

Show depth and thickness of all water, oil and gas formations. Elevation 1905'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	surface pipe	0'	353'	8 5/8"	353'	0
	casing	0'	4412'	5 1/2"	4412'	0

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4376 feet to top feet each set.

12/11 - sanded back to 4200' (92' above perfs.) 12/12 - checked top of sand - @ 4200'. Dumped 5 sx of cement on top of sand. Shot squeeze holes at 750'. Pumped 40 BBLS of water down casing-none came to surface. Pumped 110 sx cement-shut casing in. Broke old head off. Brought the 8 5/8" over the 5 1/2" w/ nipple, collar & 8 5/8" x2' swedge. Pumped 120 sx down surface, shut in. 12/13 - checked top of cement-390' down in casing, and 90' down. Ran 12 Jts-2 7/8", pumped cement

(If additional description is necessary, use BACK of this form.)

& filled casing too top. Surface took several tries. 12/16-filled sand back in surface pipe to 1' from top & filled well as filed that the same are true and correct, so help me God.

Name of Plugging Contractor Pratt Well Service, Inc. to top w/ cement.

License No. 5893

Address Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Martin Oil Producers, Inc.

C/O Tracy Black
4748 NE 160 Ave.
Cheney, KS 67025

STATE OF Kansas COUNTY OF Pratt, ss.

Steve Hart, Office Manager (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) P.O. Box 847 Pratt, KS 67124

SUBSCRIBED AND SWORN TO before me this 3 day of February, 2003

Amy S. Robertson
Notary Public

My Commission Expires: 3/13/04

AMY S. ROBERTSON
Notary Public - State of Kansas
My Appt. Expires 3/13/04

[Handwritten mark]