


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 212 No. Market
 Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 13 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNWSWK" or footage from lines NE SE SE
 Lease Owner The Bovaird Supply Company
 Lease Name McGuire "C" Well No. 2
 Office Address Box 897, Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed _____ 19____
 Application for plugging filed May 10 19 68
 Application for plugging approved _____ 19____
 Plugging commenced May 28 19 68
 Plugging completed June 3 19 68
 Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~Arenic-Elving~~ Ralph Warren
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4335 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	420'	8 5/8"	420'	none
		0	4331'	5 1/2"	4331'	3002.99

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand back to 4200' and dumped 5 sacks cement.

Set 10' rock bridge at 400' and dumped 25 sacks of cement. Filled hole with mud to 40', set 10' rock bridge and capped hole with 10 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Pipe Pullers, Inc.
 Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells
Ellinwood, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 68

My commission expires July 7, 1968

A. J. Rader
 Notary Public.

File

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1968
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

McGuire "C" #2

Loc: NE SE SE
Sec: 13-27-13w
Pratt County, Kansas
Operator: Cooperative Refinery Ass'n
Contractor: Company Rig #5

Elevation: 1891 D.P.
Casing: 8-5/8" @ 420' w/ 300 sq.
5-1/2" @ 4331' w/ 175 sq.
Comm: 6-28-53 Comp: 7-15-53
Total Depth: 4335'

From	To	Formation
0	215	Surface Hole
215	420	Shale, Shells, Red Bed
420	460	Shale
460	1180	Shale & Shells
1180	1625	Shale, Shells, Salt
1625	3020	Lime, Shale
3020	3080	Lime
3080	3180	Lime, Shale
3180	3120	Lime
3120	3625	Shale & Lime
3625	3700	Sand, Shale, Lime
3700	3800	Lime, Shale
3800	4110	Lime
4110	4110	Lime, Chert
4110	4175	Lime
4175	4200	Lime chert
4200	4210	Lime, Shale, Chert
4210	4335	Lime, Chert

(STATE OF KANSAS)
(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the McGuire "C" #2 well, located NE SE SE of Section 13-27-13w, Pratt County, Kansas.

L. M. Collins

Subscribed and sworn to before me this 7-20 day of 1953.

Clyde E. Endicott

My commission expires: 2-28-55