

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

McPherson County. Sec. 13 Twp. 27 Rge. 13 (E) (W)  
 Location as "NE/CNW/SW" or footage from lines SW NE NE  
 Lease Owner The El Dorado Refining Company  
 Lease Name Inders Well No. 5  
 Office Address Box 209 - Russell, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) oil  
 Date well completed May 4 19 54  
 Application for plugging filed September 1 19 55  
 Application for plugging approved September 2 19 55  
 Plugging commenced September 19 19 55  
 Plugging completed October 6 19 55  
 Reason for abandonment of well or producing formation Insufficient Production.

If a producing well is abandoned, date of last production September 2 19 55  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives - Box 8 - Pratt, Kansas  
 Producing formation Simpson Sand Depth to top 4292 Bottom 4340 Total Depth of Well 4340 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	480'	None
				5 1/2"	4343.74'	2,914.70'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand to 4250'  
 Run 5 sacks of cement at 4250'.  
 Mudded to 300'  
 Set rock bridge to 290'  
 Run 20 sacks of cement at 290'  
 Mudded to 35'  
 Set rock bridge to 25'  
 Run 10 sacks of cement to cap.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 29 1955  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Company  
 Address Box 558 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
 Levi B. Sherman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman  
 Box 209 - Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 19 55

My commission expires 5 - 9 - 59

PLUGGING  
 FILED SEC 13 T-320-1320  
 BOOK PAGE 46 LINE 46

Location: SW NE NE, Sec. 13-27-13W  
McPherson County, Kansas

OWNER: The El Dorado Refining Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

CABLE TOOL CONTRACTOR:

COMMENCED: 4-19-54 (w.r.)  
(w.c.t.)

COMPLETED: 5-4-54 (w.r.)  
(w.c.t.)

TOTAL DEPTH: 4340'

LOG

0-255-	Sand, Shale & Red Bed
255-480-	Sand, Shells, Shale & Red Bed
480-640-	Shale & Red Bed
640-780-	Anhydrite
780-1100	Shale
1100-1725	Shale & Shells
1725-1860	Lime
1860-3185	Shale & Lime
3185-4115	Lime
4115-4172	Conglomerate
4172-4203	Shale
4203-4225	Lime Viola
4225-4244	Lime
4244-4292	Core #1
4292-4340	Simpson Sand, T.D.

CASING RECORD

Ran 480' of 8 5/8"  
Casing, Set with 350  
sacks of cement.

Ran 4343.74' of 5 1/2"  
Casing, set with 75 sacks  
of bulk cement.

Brief Plugging Record on  
El Dorado Refining Company's  
Luders Well # 5 in  
McPherson County, Kansas

Total Depth 4340'  
5 1/2" Casing Set at 4343.74'  
Cemented with 75 sacks  
8 5/8" Casing set at 480'  
Cemented with 350 sacks.

Filled hole with sand to 4250'  
Run 5 sacks of cement at 4250'  
Mudded to 300'  
Set rock bridge to 290'  
Run 20 sacks of cement at 290'  
Mudded to 35'  
Set rock bridge to 25'  
Run 10 sacks of cement to cap.

Work Started September 19, 1955  
Work Completed October 6, 1955

C. E. Shull Casing Pulling Company  
Box 558  
Great Bend, Kansas

License No. 8

**PLUGGING**  
FILE SECL 3 727 R 13W  
BOOK PAGE 46 LINE 45

**RECEIVED**  
OPERATION COMMISSION  
OCT 19 1955  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG

LUDERS #5

Location: SW NE NE, Sec. 13-27-13W  
McPherson County, Kansas

OWNER: The El Dorado Refining Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

CABLE TOOL CONTRACTOR:

COMMENCED: 4-19-54 (w.r.)  
(w.c.t.)

COMPLETED: 5-1-54 (w.r.)  
(w.c.t.)

TOTAL DEPTH: 4310'

LOG

CASING RECORD

0-255	Sand, shale & red bed.
255-480	Sand, Shells, Shale & Red bed.
480-640	Shale & Red Bed
640-780	Anhydrite
780-1100	Shale
1100-1725	Shale & Shells
1725-1860	Lime
1860-3185	Shale & Lime
3185-4115	Lime
4115-4172	Cong.
4172-4203	Shale
4203-4225	Lime Via.
4225-4244	Lime
4244-4292	Core #1
4292-4340	Simpson Sand, T. D.

Ran 480' of 5 5/8" casing  
set with 350 sacks of cement.

Ran 4313.74' of 5 1/2"  
casing, set with 75 sacks  
of bulk cement.

RECEIVED  
REGISTRATION COMMISSION

SEP 2 1955

**PLUGGING**  
 REG. SEC 13 27 R 13 OBSERVATION DIVISION  
 WICHITA, KANSAS  
 BOOK PAGE 146 LINE 45