

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20,124-0000

LEASE NAME SHEEGOG

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

990 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Bowers Drilling Co., Inc.

SEC. 2 TWP. 27S RGE. 13 (E) or (W)

ADDRESS 125 No. Market

COUNTY Pratt

PHONE#(316) 262-6449 OPERATORS LICENSE NO. 5435

Date Well Completed Apr. 1969

Character of Well Oil (depleted)

Plugging Commenced 7-30-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-1-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? no If not, is well log attached? Yes

Producing Formation Lansing KC Depth to Top 3741 Bottom 4064 T.O. 4440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	clay & shale	0	425	8-5/8	425	0
Lansing KC	oil & water	3741	4064	5-1/2	4400	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Fill sand to 3700' w/dump, & 4 sax cement. Heavy mud to 775', plug w/30 sax cement. Plug at 425' w/25 sax cement. Plug at 60' w/10 sax cement. Pumped 100 sax cement down annulus, max. press. 175#, shut in pressure 50#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc License No. 5435

Address Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Emil E. Bowers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1986

Judy C. Ridder
Notary Public

My Commission Expires: March 2, 1988

JUDY C. RIDDER
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 3/2/88

8-25-86
AUG 25 1986

Form CP-4
Revised 08-84

WELL LOG

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Sheegog #2
 LOCATION: Approx. 100' East of SW NW SE
 Section 2-27S-13W
 Pratt County, Kansas
 COMMENCED: April 7, 1969
 COMPLETED: April 21, 1969
 ELEVATION: 1920 Kelly Bushing

0 - 200	Sand clay	
200 - 828	Redbed	Set 8-5/8" casing at 421 w/375 sacks
828 - 1220	Shale	
1220 - 1785	Redbed, shale and shells	
1785 - 2037	Shale and shells	
2037 - 3750	Lime and shale	
3750 - 4070	Lime	
4070 - 4145	Lime and shale	
4145 - 4267	Lime	
4267 - 4382	Lime and shale	
4382 - 4440	Lime	Set 5 1/2" casing at 4439 w/175 sacks
4440	T. D.	

LOG TOPS:

Topoka	3205	Mississippi	4174
Heebner	3548	Viola	4222
Douglas	3588	Simpson Shale	4258
Brown Lime	3713	Simpson Dolomite	4270
Lansing	3741	Simpson Sand	4286
Base/Kansas City	4066	Arbuckle	4365

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sheegog #2 located Approx. 100' East of SW NW SE Section 2-27S-13W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, this 29th day of April, 1969.

Donna F. Brown, Notary Public

My Commission expires 2-10-73

RECEIVED
 STATE OF KANSAS COMMISSION
 DONNA F. BROWN, NOTARY PUBLIC

AUG 25 1980