

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-151-20135-0000

API NUMBER N/A

LEASE NAME BRIEGEMAN

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1320 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 2 TWP. 27 SRGE. 13 (E) or (W)

COUNTY PRATT

Date Well Completed 12-14-69

Plugging Commenced 10-30-87

Plugging Completed 10-30-87

LEASE OPERATOR Bowers Drilling Co., Inc.

ADDRESS 125 No. Market, Wichita, Ks. 67202

PHONE (316) 262-6449 OPERATORS LICENSE NO. 5435

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation Lansing Kc. Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LANS. KC	oil	0	1000	8 5/8	1000	0
		0	4370	5 1/2	4370	2110

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole w/ sand to 3400' w/ 5 SACK CEMENT. Pulled 2110' casing, plugged WITH 4 SACK HULLS AND 100 SACK THIRTY MIX CEMENT by B.D.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc. License No. 5435

Address 125 No. Market, Suite 1425, Wichita, Ks. 67202

STATE OF KANSAS COUNTY OF Sedgwick, ss. CONSERVATION DIVISION  
Wichita, Kansas

Emil E. Bowers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) WICHITA, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 87

Judy C. Ridder  
Notary Public  
STATE CORPORATION COMMISSION

My Commission Expires:

JUDY C. RIDDER  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY APPT. EXP. 3/2/88

Notary Public  
STATE CORPORATION COMMISSION

11-19-87  
NOV 19 1987

Form CP-4  
Revised 08-84

CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG

COMPANY: Bowers Drilling Company, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Briggeman #1  
 LOCATION: C E/2 E/2 SW/4  
 Sec. 2-27S-13W  
 Pratt County, Kansas  
 COMMENCED: October 7, 1969  
 COMPLETED: October 19, 1969  
 ELEVATION: 1927 Kelly Bushing  
 1925 Derrick Floor  
 1921 Ground Level

0 - 215	Sand & chalk	
215 - 468	Shale & Lime	
468 - 1145	Shale	Set 8 5/8" casing at 910'
1145 - 1300	Shale	w/575 saks
1300 - 3425	Shale & Lime	
3425 - 3565	Lime	
3565 - 3835	Shale & Lime	
3835 - 4283	Lime	
4283 - 4295	Lime & sand	
4295 - 4375	Shale & Lime	
4375 - 4383	Lime	Set 5 1/2" casing at 4370'
4383	T.D.	w/175 saks.

LOG TOPS:

Topeka	3217
Heebner	3554
Douglas	3593
Brown Lime	3717
Lansing	3746
Base/Kansas City	4065
Mississippian	4174
Viola	4218
Simpson	4248
Simpson Dolomite	4258
Simpson Sand	4277
Arbuckle	4353

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 19 1987  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )


I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Briggeman located C E/2 E/2 SW/4 Section 2-27S-13W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*  
 Emil E. Bowers, President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, this 26th day of November, 1969.

*Carole A. Young*  
 Carole A. Young, Notary Public

My commission expires May 12, 1973



RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 19 1987  
 CONSERVATION DIVISION  
 Wichita, Kansas