

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 31 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNW%SW%" or footage from lines NW SE SE SE
Lease Owner Sterling Drilling Company, et al
Lease Name Sterling, Kansas Greenstreet Well No. 3
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 13, 1956
Application for plugging filed November 13, 1956
Application for plugging approved November 13, 1956
Plugging commenced November 13, 1956
Plugging completed November 13, 1956
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	360'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Bottom plug at 300' with 20 sacks cement. Heavy mud to 35', set second plug with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company
Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 56

My Commission Expires Jan. 22, 1958

My commission expires _____

Bernard Lander milk
Notary Public.
CORPORATION COMMISSION

PLUGGING
 FILE SEC. 31 T. 27 R. 13W
 BOOK PAGE 116 LINE 5
 NOV 14 1956 11-14-56
 CONSERVATION DIVISION
 Wichita, Kansas

GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG-----GREENSTREET #3

Location: SE SE SE, Section 31-27S-13W,
Pratt County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 10-27-56 (w.r.)
COMPLETED: 11-12-56 (w.r.)

TOTAL DEPTH: 4420'

LOG

0-80	Sand
80-360	Red Bed
360-880	Red Bed & Shale
880-905	Anhydrite
905-1475	Sand & Shale
1475-1820	Shale & Limestone
1820-2150	Limestone
2150-2260	Limestone & Shale
2260-2560	Limestone
2560-3020	Limestone & Shale
3020-3355	Limestone
3355-3620	Limestone & Shale
3620-3755	Shale
3755-3845	Limestone & Shale
3845-4190	Limestone
4190-4240	Limestone & Shale
4240-4275	Limestone
4275-4325	Limestone & Shale
4325-4360	Limestone
4360-4420	Coring Simpson T.D.

CASING RECORD

Ran 360' of 8-5/8" casing set with
250 sacks cement, 2 sacks calcium
chloride.

PRODUCTION

Plugged & Abandoned

PLUGGING
FILE SEC. 31 T. 27 R. 13W
BOOK PAGE 116 LI E 5

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1956

CONSERVATION DIVISION
Wichita, Kansas