

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed June 7, 1967.

Operator's Full Name Graybol Oil Corporation
Complete Address 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103
Lease Name Antrim Well No. # 1
Location C SW NE Sec. 30 Twp. 27 Rge. 9 (E) (W)W
County Kingman Total Depth 4415'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Graybol Oil Corporation

Address 2200 National Bank of Tulsa, Tulsa, Okla. License No.

Operation Completed: Hour 4:00 P.M. Day 27th Month June Year 1967

The above well was plugged as follows:

304' of 8 5/8" surface pipe, cement circulated with 195 sacks. Hole was
filled with drilling mud to 300', bridged with 2 sacks of dry cement and
1/2 sack of hulls on fluid at 300', and cemented with 23 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack
of dry cement and 1/2 sack of hulls, and cemented with 9 sacks to the base
of the cellar. Rat holle bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/3/67
INV. NO. 5511-W

Signed: Archie Elving
Well Plugging Supervisor