

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-095-21,072-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Publishers Petroleum, Inc.

Complete Address Box 25125, Oklahoma City, Oklahoma

Lease Name Osner Well No. 2

Location SE SE NE Sec. 35 Twp. 27 Rge. 8W (East) (West)

County Kingman Total Depth 3750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor H-30 Drilling Rig #27

Address 251 North Water, Wichita 67202 License No. _____

Operation Completed: Hour: 8:30PM Day: 6 Month: 7 Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

350' of 8 5/8" SP W/300 sx

Total of 117 sx of 50-50 poz-mix 4% gel 3% cc

50 sx @ 620'

40 sx @ 350'

Bridge & 10 sx @ 40'

10 RH 5MH 2 WW Cemented by Howco

RECEIVED
STATE CORPORATION

AUG 28 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. J. Deslier
Conservation Division Agent

DATE 8-26-81

INV. NO. 6300-W

121-88

KANSAS DRILLERS LOG

COMPANY Publishers Petroleum Co.

SEC. 35 T. 27S R. 8W

FARM Osner

NO. 2

LOC. SW SE NE

COUNTY Kingman

ROTARY TOTAL DEPTH 3,750'

COMM. June 30, 1981

COMP. July 6, 1981

CONTRACTOR H-30, INC. (Rig #77)

ISSUED July 15, 1981

CASINO

10 3/4"

8 5/8" Set at 356' cemented w/300 sxs cement

ELEVATION 1,612' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	47'
Sand and Shale	367'
Red Bed	1,472'
Anhydrite and Shale	1,535'
Shale and Anhydrite	1,800'
Shale	2,027'
Lime and Shale	2,321'
Shale and Lime	2,453'
Lime and Shale	2,910'
Shale and Lime	3,397'
Lime and Shale	3,590'
Lime	3,722'
Lime and Shale	3,750'
Rotary Total Depth	3,750'

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Gary Younger

Gary Younger

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 15th day of July, 1981.

Helen Pracht

Helen Pracht - Notary Public

My Commission Expires:

June 4, 1985

