

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shallow Water Refining Co. % Maurice L. Brown

Complete Address 1500 Vickers KSB & T Bldg. Wichita, Ks

Lease Name Fitzsimmons Well No. 1

Location SE/SE/NW Sec. 30 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4561

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 1:00 PM Day 18 Month 9 Year 1970

The above well was plugged as follows:

379 ft of 8 5/8 surface pipe cemented with 250 sacks. 4445 ft of

5 1/2 long string cemented with 125 sacks. Top perf. 4069 ft. Sand

back to 4000 ft, 5 sacks cement with bailer. Pulled 3200 ft of 5 1/2.

Set 10 ft. rock bridge at 365 ft. Fill hole with 5 yds redimix to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell B. Hunter

Well Plugging Supervisor

DATE 9-21-70INV. NO. 2568-W