

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Kiowa County. Sec. 7 Twp. 27 Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Pickrell Drilling Company

Lease Name Parton "B" Well No. 1

Office Address 705 Fourth National Bank Bldg., Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed March 28 19 74

Application for plugging filed March 28 19 74

Application for plugging approved March 28 19 74

Plugging commenced March 28 19 74

Plugging completed March 28 19 74

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Ks.

Producing formation Depth to top Bottom Total Depth of Well 4852 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	222'	None

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1974
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug 500' 40 sacks

Middle Plug 200' 25 sacks

Top Plug 40' 10 sacks

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK ss.

C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts

705 Fourth National Bank Bldg., Wichita, Ks. 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1974

My commission expires August 19, 1975

Helen L. Martin

Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 3/16/74

Rotary Drilling Completed 3/28/74

LOCATION: Parton "B" No. 1
C NE NE Section 7-27S-19W
Kiowa County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (5 jts) new 20# 8 5/8" surface casing set at 222' and cemented with 190 sacks cement. Circulated. Completed 3:15 PM, 3/16/74. D & A., plugged March 28, 1974.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

175	Top Soil, Sand	<u>C. F. S.</u>
222	Shale	4206
1080	Shale & Shells	4590
1266	Shale	4800
1284	Anhydrite	4825
1695	Shale	4835
2095	Shale & Shells	4845
2385	Lime & Shale	
2540	Shale & Lime Stringers	
2615	Shale & Lime	
2655	Lime & Shale & Sand	
2955	Lime & Shale	
3115	Shale & Lime Streaks	<u>Slope Tests</u>
3395	Lime & Shale	2500
3540	Shale & Lime Streaks	3000
3670	Limey Shale	3500
3755	Shale & Lime	4000
3830	Sandy Lime	4500
4130	Lime & Shale	
4195	Shale	
4215	Lansing	
4365	Lime & Shale	
4385	Lime	
4415	Shale with Lime Streaks	
4455	Lime with Shale Streaks	
4797	Shale & Lime	
4852	RTD, Mississippi	

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1974
CONSERVATION DIVISION
Wichita, Kansas

	<u>S. L. M.</u>
Board	4291.52
Strap	4288.61
Diff.	2.91

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By *[Signature]*
C. W. Sebits Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 2nd day of April, 19 74, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 19, 1974

Helen L. Martin
Helen L. Martin Notary Public