

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 14 Twp. 27S Rge. 19W (E) (W)

Location as "NE/CNW'SW" or footage from lines C SE SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Cummings Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 5, 19 57

Application for plugging filed May 5, 19 57

Application for plugging approved May 5, 19 57

Plugging commenced May 5, 19 57

Plugging completed May 5, 19 57

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4851 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	4-19-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set No. 1 plug at 350' with 1/2 sack hulls and 20 sacks cement. Set No. 2 plug at 40' with 1/2 sack hulls and 10 sacks cement.

Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 903 Union National Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P

903 Union National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of May, 1957

My commission expires December 19, 1960

Louetta M. Duncan Notary Public.

STATE CORPORATION COMMISSION

5-10-57  
MAY 11 1957

PLUGGING  
FILE SEC 14 T 27 R 19W  
BOOK PAGE 11 LINE 9

CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
903 Union National Building  
Wichita, Kansas

Cummings No. 1  
C SE SW Sec. 14-27S-19W  
Kiowa County, Kansas

Total Depth: 4851'

Elevation: 2234' RB  
Production: D & A

Commenced: 4-19-57 Completed: 5-6-57

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 500' with 450 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Shale	495'		<u>TOPS</u>	
Anhydrite	525'			
Shale & Shells	2350'	Heebner	4019'	(-1785)
Shale & Lime	4200'	Toronto	4052'	(-1818)
Lime	4777'	Lansing	4185'	(-1951)
Cherty Lime	4851'	Base K.C.	4508'	(-2274)
Total Depth	4851'	Conglomerate	4748'	(-2514)
		Miss. Chert	4772'	(-2538)
		Miss. Lime	4814'	(-2580)
		Total Depth	4851'	(-2617)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *Alan P. [Signature]*  
Vice-President

Subscribed and sworn to before me this 9th day of May, 1957.

My Commission Expires:

December 19, 1960

RECEIVED  
STATE COMMISSION

MAY 10 1957

CONSERVATION DIVISION  
Wichita, Kansas

*Lucretia M. [Signature]*  
Notary Public

PLUGGING  
FILE SEC. 14 T. 27 R. 19W  
BOOK PAGE 11 LINE 9