

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-095-00935-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Matson

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div. SE NE SE Ft. from S Section Line  
\_\_\_\_\_ Ft. from E Section Line

LEASE OPERATOR Howard Alexander

SEC. 32 TWP. 29S RGE. 6W (E) or (W)

ADDRESS 420 S. Main Tulsa, Oklahoma 74103

COUNTY Kingman

PHONE# ( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

Date Well Completed 9-18-57

Character of Well \_\_\_\_\_

Plugging Commenced 12-10-84

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-12-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Steve Van Cieson

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	185	none
				7"	3757	2584

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 04 1985  
2-4-85  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pump 35 sks. of cement @ 3670 to 3450

Pump 137 sks. of cement @ 245

Cut off & cap 10 3/4 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sarzens Casing Pulling Service License No. 647

Address Box 506 Liberal, Kansas 67901

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Howard Alexander

(Address) 420 S. MAIN TULSA, OK 74103

SUBSCRIBED AND SWORN TO before me this 1<sup>st</sup> day of February, 19 85

Delva L. Zuniga  
Notary Public

My Commission Expires: May 20, 1986

WELL RECORD

MATSON #2 15-095-00935-00-00  
 SE NE SE Sec. 32-29S-6W  
 Kingman County, Kansas

Company : McKnab & Lindsay  
 Contractors: McKnab & Lindsay

Comm: 5/22/57  
 Under Surface: 5/24/57  
 Comp: 6/3/57

Driller's Log:

Sand & Shale	0	185
Lime	185	204
Lime & ANH	204	250
Shale	250	1015
Lime, Shale, & ANH	1015	1110
Lime & Shale	1110	2683
Lime	2683	2892
Lime & Shale	2892	3290
Sandy Lime	3290	3374
Lime	3374	3760
T.D.		3760

Cement and Casing Record:

6 jts. 10 3/4" surface pipe (135'), one  
 guide shoe, 1 - 10 3/4" centralizer cemented  
 with 175 sacks of Halliburton cement and  
 4 sacks calcium chloride.

130 joints 7" 5mls. casing 24th  
 10 A THRD Set with 100 sacks of Halliburton  
 pozmix cement.

APPROVED:  
 McKnab and Lindsay Drilling Contractors  
 By E. J. Lindsay  
 Date June 21, 1957

Subscribed to and sworn before me this 21st day of June, 19 57

My commission expires August 21, 1957

Melvin Libbans  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 09 1984

CONSERVATION DIVISION  
 Wichita, Kansas