

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-095-00936-00-00

API NUMBER _____

LEASE NAME Matson

TYPE OR PRINT

WELL NUMBER 3

NOTICE: Fill out completely
and return to Cons. Div. NE NE SE Ft. from S Section Line
_____ Ft. from E Section Line

LEASE OPERATOR Howard Alexander

SEC. 32 TWP. 29S RGE. 6W (E) or (W)

ADDRESS 420 S. Main Tulsa, Oklahoma 74103

COUNTY Kingman

PHONE# () _____ OPERATORS LICENSE NO. _____

Date Well Completed 12-2-59

Character of Well _____

Plugging Commenced 12-5-84

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-7-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Steve Van Gieson

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8"	309	none
				5 1/2"	3747	2814

RECEIVED
STATE CORPORATION COMMISSION
FEB 04 1985

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pump 25 sks. of cement @ 3696 to 3420

Pump 115 sks. of cement @ 310

Cut off & can 8" 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901

STATE OF _____ COUNTY OF _____, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Howard Alexander

(Address) 420 S. MAIN, TULSA, OK 74103

SUBSCRIBED AND SWORN TO before me this 1st day of FEBRUARY, 19 85

Richard L. Zuniga
Notary Public

My Commission Expires: May 20, 1986

15-095-00936-00-00

ROTARY DRILLING LOG

OPERATOR: Petroleum Management, Inc.
MATSON NO. 3
NE NE SE Sec. 32-29-5W,
Kingman County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
CORP: 9/1/59
COMP: 9/12/59

Remarks: Set 8-5/8" at 260' cemented
with 200 sx. HA-500 cement

Formations:

Shale & Shells	170'
Shale & Lime	260'
Shale & Lime Streaks	1050'
Lime Streaks	1164'
Lime	1574'
Lime & Shale	1942'
Shale & Sand	2100'
Shale & Lime Streaks	2295'
Lime & Shale	2430'
Shale & Lime	2728'
Lime	2900'
Shale	2970'
Lime	2990'
Lime & Shale	3175'
Lime	3224'
Lime & Shale	3450'
Shale & Lime	3498'
Lime & Shale	3533'
Lime	3619'
Lime, some chert	3645'
Lime	3750'
Rotary Total Depth	3750'

Set 5-1/2" casing at 3747' cemented with
150 sacks of 60-40 Formix.

We certify the above log is true and correct
to the best of our knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol