

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,380-000

LEASE NAME COLBORN

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-10

660' Ft. from S Section Line

3300' Ft. from E Section Line

SEC. 10 TWP. 33S RGE. 11 (X) or (W)

COUNTY BARBER

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd North, Bldg. 300 Wichita, KS. 67226

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 9-20-91

Plugging Commenced 9-20-91

Plugging Completed 9-20-91

The plugging proposal was approved on September 20, 1991 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	284'	8 5/8"	284'	none

SEP 27 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

50 sx. @ 650', 50 sx. @ 310', 10 sx. @ 40', 15 sx. in rathole

TOTAL: 125 sx. 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. DRILLING, INC. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VESS OIL CORPORATION

STATE OF KANSAS COUNTY OF BARTON, ss.

Greg Davidson (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, KS.



SUBSCRIBED AND SWORN TO before me this 24th day of September, 1991

Bessie M. DeWerff

Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93

ORIGINAL

DRILLER'S WELL LOG

COMMENCED: September 12, 1991
COMPLETED: September 20, 1991

0 - 284 Surface
284 - 1615 Shale
1615 - 3085 Shale & Lime
3085 - 4302 Lime & Shale
4302 - 4600 Lime
4600 RTD

VESS OIL CORPORATION
Colborn #1-10
SE SW Sec. 10T33S-R11W
Barber County, Kansas

ELEVATION: 1485' GL 1490' KB

FORMATION DATA (sample)

Heebner	3600' (-2110)
Br. Lime	3801' (-2311)
Lansing	3810' (-2320)
BKC	4309' (-2819)
Miss.	4473' (-2983)
Miss. Chert	4520' (-3030)
RTD	4600' (-3110)

SURFACE CASING:

8 5/8" set at 284' W/180 sx.
60/40 Poz. 2% Gel, 3% CC

A F F I D A V I T

RECEIVED
STATE CORPORATION COMMISSION

SEP 06 1992

CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS)
COUNTY OF BARTON) ss


GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 24th day of September, 1991

My Commission expires: 5-20-93

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff



SEP 27 1991

DRILLER'S WELL LOG

COMMENCED: September 12, 1991
COMPLETED: September 20, 1991

- 0 - 284 Surface
- 284 - 1615 Shale
- 1615 - 3085 Shale & Lime
- 3085 - 4302 Lime & Shale
- 4302 - 4600 Lime
- 4600 RTD

REGISTRATION DIVISION
 VESS OIL CORPORATION - Wichita, Kansas
 Colborn #1-10
 SE SW Sec. 10T33S-R11W
 Barber County, Kansas

ELEVATION: 1485' GL 1490' KB

FORMATION DATA (sample)

Heebner	3600' (-2110)
Br. Lime	3801' (-2311)
Lansing	3810' (-2320)
BKC	4309' (-2819)
Miss.	4473' (-2983)
Miss. Chert	4520' (-3030)
RTD	4600' (-3110)

SURFACE CASING:

8 5/8" set at 284' W/180 sx.
60/40 Poz. 2% Gel, 3% CC

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 24th day of September, 1991

My Commission expires: 5-20-93

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

