

15-007-19120-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barber County. Sec. 10 Twp. 33S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines 990' FWL & 1650' FSL
Lease Owner Amerada Hess Corporation
Lease Name A. H. Colborn Well No. 1
Office Address P. O. Box 591, Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Gas Well
Date well completed 4-10-56 19
Application for plugging filed 8-31-71 19
Application for plugging approved 9-2-71 19
Plugging commenced 10-1-71 19
Plugging completed 10-5-71 19
Reason for abandonment of well or producing formation Well Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production December 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. G. Russell Biberstein
Producing formation Mississippi Depth to top 4516' Bottom 4558' Total Depth of Well 4625' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Gas	4516'	4558'	8-5/8"	307'	None
				5-1/2"	4623'	3427'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4430' feet to 4500' feet for each plug set.

Pulled 2-3/8" od tubing. Rockhold Casing Pullers set bottom hole plug in 5-1/2" casing from 4430' to 4500'. Shot off 5-1/2" casing at 3410'. Pulled and recovered total of 82 jts. 5-1/2" od 15.5# J-55 R-3 8RT SS casing for 3427.20'. Put 4 yards re-mix in top of surface casing, from 300' to surface. Cut of surface casing and welded plate on top of surface casing. Finished P & A 10-5-71.
Work performed under the direction of Mr. G. Russell Biberstein, Attica, Kansas, representative of Kansas Corporation Commission.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering Company
Address P.O. Box 698, Great Bend, Kansas 67530

STATE OF Texas, COUNTY OF Midland, ss.
B. J. Sinex (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B.J. Sinex
P.O. Box 591, Midland, Texas 79701
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1971

My commission expires 6-1-73

J.H. Driver J.H. DRIVER
Notary Public.
Midland County, Texas

AMERADA PETROLEUM CORPORATION

WELL SUMMARY
FORMATION DATA

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1972
CONSERVATION DIVISION
Wichita, Kansas

WELL A. H. Colborn

NO 1

FIELD Rhodes Pool

DRILLER'S LOG:

<u>From</u>	<u>To</u>	
0'	312'	Red Bed.
312'	700'	Shale.
700'	1082'	Shale & Shells.
1082'	1570'	Shale & Lime.
1570'	1670'	Anhydrite & Shale
1670'	1720'	Shale & Lime.
1720'	1852'	Shale & Shells.
1852'	2128'	Shale & Lime.
2128'	2215'	Lime & Shale.
2215'	2435'	Shale.
2435'	3002'	Shale & Lime.
3002'	3192'	Lime & Shale.
3192'	3622'	Shale & Lime.
3622'	3719'	Lime & Shale.
3719'	3820'	Sandy Lime.
3820'	4224'	Lime.
4224'	4267'	Lime & Shale.
4267'	4367'	Lime.
4367'	4396'	Lime & Shale.
4396'	4460'	Lime.
4460'	4525'	Lime & Shale.
4525'	4570'	Lime & Chert.
4570'	4588'	Chert & Shale.
4588'	4625'	Lime.
T.D.	4625'	

GEO. TOPS:

Heebner	- 3593'
Toronto	- 3615'
Douglas Shale	- 3624'
Douglas Sand	- 3710'
Brown Lime	- 3800'
Lansing	- 3806'
Mississippi	- 4480'

SCHLUMBERGER TOPS:

Heebner	- 3601'
Toronto	- 3611'
Douglas	- 3630'
Douglas Sand	- 3715'
Brown Lime	- 3806'
Lansing	- 3812'
R.W. Mississippi	- 4485'
Mississippi Cherty Lime	- 4496'
Kinderhook	- 4597'
Schlumberger T.D.	- 4626'