

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Barber County. Sec. 11 Twp. 33S Rge. 11 XXXX (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE SE
Lease Owner Magnolia Petroleum Co., Box 900, Dallas, Texas
Lease Name Lloyd DAVIS Well No. 1
Office Address Box 770 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed March 25, 1954 19
Application for plugging filed March 25, 1954 (via telephone) 19
Application for plugging approved March 25, 1954 (via telephone) 19
Plugging commenced March 26, 1954 19
Plugging completed March 26, 1954 19
Reason for abandonment of well or producing formation Well drilled dry -
No shows
If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Horner of Great Bend, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 5100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	480'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole mudded w/heavy mud from bottom to 300' from top; Halliburton plug spotted @ 300',
cemented w/25 sx cmnt by Halliburton, filled hole w/heavy mud from 300' to 30' from top,
filled hole from 30' from top to top of surface csg w/38 sx cmnt. Rat hole plugged
w/cmnt.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling Company
Address Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON
C. A. HILL (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Hill

Box 770 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of March, 1954
My commission expires Jan. 14, 1957
Harriett S. Kaiser Notary Public.

23-8390-6 6-51-20M
PLUGGING
FILE SEC 11 T 38 R 11W
BOOK PAGE 23 LINE 6
RECEIVED
MAR 30 1954
3-30-54
CONSERVATION DIVISION
Wichita, Kansas

Well Log

Name of Well: Lloyd DAVIS #1 Drilled Dry and Abandoned 3-26-54
Location: SE SE SE
 Sec. 11-33S-11W
 Barber County, Kansas

OWNER: MAGNOLIA PETROLEUM COMPANY
 Box 900, Dallas, Texas

Chase District Kansas

Location Staked: 2-16-54 Drilled by: Barnett Drilling Co., Wichita, Kan.
Spud Date: 2-19-54 Plugged by: " " "
Completed Drilling 2-25-54
Plugged: 2-26-54


13 3/8" casing set @ 480' w/600 sx cmnt. circ. 2-20-54

Clay, sand and shale	0	265	Shale & lime	4295	4480
Red Bed	265	430	Lime	4480	4645
Shale	430	480	Lime & shale	4645	4660
Red Bed, shale & shells	480	800	Shale & lime	4660	4695
Shale & shells	800	1320	Lime & shale	4695	4779
Shale	1320	1520	Shale	4779	4800
Anydrite	1520	1560	Lime	4800	4895
Lime & shale	1560	2145	Lime, Shale & sand	4895	4915
Shale & lime	2145	2325	Sand	4915	4925
Shale	2325	2430	Shale, Lime & sand	4925	4955
Shale & lime	2430	2510	Lime & shale	4955	4995
Shale	2510	2625	Shale & lime	4995	5019
Shale & Lime	2625	2810	Shale, Lime & sand	5019	5040
Shale	2810	2880	Conglomerate	5040	5060
Lime & shale	2880	2950	Lime	5060	5100 TD
Lime	2950	3396			
Shale & lime	3396	3450	TOTAL DEPTH DRILLED:	5100'	
Shale & sand	3450	3496	OIL STRING SET@ :	None	
Shale & shells	3496	3530	PLUG BACK DEPTH:	D & A	
Shale & lime	3530	3795			
Lime	3795	4045			
Lime & shale	4045	4065			
Lime	4065	4295			

Well drilled under the supervision of R. M. Capps, Magnolia Petroleum Co. Foreman.

DST #1 3466-3496 op 1 hr, fair blow 15 min, weak blow 18 min, recov. 55' DM, NS, IFP
20# FFP 40# SIBHP 40# in 20 min.

DST #2 3691-3703 op 1 hr, fair blow remained thruought test, recov. 360' MSW, IFP 20# F
FFP 165# SIBHP 1365# in 20 min.



FILED
OCT 10 1954

WICHITA
KANSAS