

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20938-000

LEASE NAME Rice "D"

WELL NUMBER 4

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 31 TWP. 27S RGE. 18 (EX) (W)

COUNTY Kiowa

Date Well Completed 4/6/83

Plugging Commenced 12/5/00

Plugging Completed 12/6/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 7570 W. 21st-Bldg. 1010-D, Wichita, Ks.

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top _____ Bottom _____ T.D. 4845

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	498'	-0-
				4 1/2	4843'	2896.9

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Set cast iron bridge plug @ 4500', dump 25 sacks on plug. Pull pipe to 1200'; pump 10 sacks gel and 50 sacks cement. Pull to 510', pump 50 sacks cement out. Pull to 40' circulate 10 sacks to surface. All cement 60/40 Posmix/w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.


STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (Employee of Operator or) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D
Wichita, Ks. 67205

CRIBED AND SWORN TO before me this 3rd day of January, 2000



Judith K. Moser
Notary Public

My Commission Expires: May 17, 2001

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2001
CONSERVATION DIVISION
WICHITA, KS

