


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County, Sec. 31 Twp. 27 Rge. 18W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NE SW

Lease Owner TGT Petroleum Corporation  
Lease Name RICE "A" Well No. 1  
Office Address 209 E. William, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plot

Date Well completed Feb. 4 1980  
Application for plugging filed(verbally) Feb. 4 1980  
Application for plugging approved(verbally) Feb. 4 1980  
Plugging commenced Feb. 4 1980  
Plugging completed Feb. 4 1980

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 5000'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 5000'  
Set 1st plug at 600' with 40 sacks  
2nd plug at 330' with 40 sacks  
3rd plug at 40' solid bridge with 10 sacks rathole with 5 sacks.  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 8:25 p.m., 02-04-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1980



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1980  
2-13-80  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: TGT Petroleum Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Rice "A" #1  
 LOCATION: C NE SW, Section 31-27-18  
 Kiowa County, Kansas  
 SPUD DATE: January 10, 1980  
 COMPLETION DATE: February 04, 1980

0	254	Sand
254	350	Shale and sand
350	973	Shale and red bed
973	2125	Shale and lime
2125	5000	Lime and shale
	5000	Rotary Total Depth

Spud hole at 12:00 midnight, January 10, 1980. Drilled 360' of 12 1/4" hole. Ran 9 joints of 8-5/8" - 28# casing. (Talley 357.95'). Set at 349' with 350 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:30 p.m., January 11, 1980.

T.D. 5000'. Set 1st plug at 600' with 40 sacks, 2nd plug at 330' with 40 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 8:25 p.m., February 04, 1980.

SAMPLE TOPS:

Anhydrite 1195'  
 B/Anhydrite 1218'

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 13 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Rice "A" #1, C NE SW, Section 31-27-18, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 11th day of February 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.