

15-097-20647-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Rice

WELL NUMBER D-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 27 RGE. 18 (E) or (W)

COUNTY Kiowa

Date Well Completed

Plugging Commenced 7-27-92

Plugging Completed 7-30-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR T G T Petroleum Corp.

ADDRESS 209 E. Williams #615 Wichita, Kansas 67202

PHONE# (316) 262-6489 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4851'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	360'	none
				4 1/2"	4850'	2539'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4718', ran 4 sacks cement. Shot pipe @3500', 3200', 2950', 2539'. Pumped down 8 5/8" 300# hulls, 10 gel, 50 sacks cement, 10 sacks gel, 100# hulls, 150 sacks cement, 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: T G T Petroleum Corporation

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 5 day of August 1992

Irene Herzberg
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1992
CONSERVATION DIVISION
Wichita, Kansas

APR 1 1981

CONTRACTOR'S WELL LOG

OPERATOR: TGT Petroleum Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: RICE "D" #2
 LOCATION: 300' N & ~~SW/SW~~ Section 31-27S-18W
 120' E Kiowa County, Kansas
 SPUD DATE: C SW NE 2/26/81
 COMPLETION DATE: 3/17/81

0	365	Redbed & Shale
365	765	Redbed
765	1435	Shale
1435	5000	Lime & Shale
	5000	Rotary Total Depth

Spud hole @ 9:00 a.m., 2/26/81. Drilled 365' of a 12 1/4" hole. Ran 9 jts. of 8 5/8" - 24# casing (tally 349.89 overall) Set @ 360' with 350 sx. of common, 3% c.c., 2% gel.

T.D. @ 5000'. Ran 150 jts. of 4 1/2" - 10 1/2# casing (tally 4856') Set @ 4855'. Cemented with 50 sx. of Halco Lite, 12 1/2# gilsinite per sack, 225 sx. of 50-50 posmix, 2% gel. Plug was down @ 8:45 a.m., 3/17/81.

SAMPLE TOPS:

Anhydrite 1170'
 B/Anhydrite 1200'


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc, does hereby state that the above and foregoing is a true and correct copy of the log of the RICE "D" #2, SW/SW, Section 31-27S-18W, Kiowa County, Kansas. 300' N & 120' E C SW NE

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 31st day of March, 1981.



Suzanne M. Hofer
 Suzanne M. Hofer, Notary Public

2/4/85

RECEIVED
 STATE CORPORATION COMMISSION

JUL 10 1992

CONSERVATION DIVISION
 Wichita, Kansas