

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR T G T Petroleum Corp.

ADDRESS 155 N. Market, Suite 820 Wichita, KS 67202

PHONE# (316) 262-6489 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4851'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	366	none
				5 1/2	4851'	2560'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4126' & 5 sks cement. Shot @ 3402, 3260, 2941, & 2560. Pulled pipe.

Plugged well with 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 100# hulls, 8 5/8 plug, 150 sks cement. 60/40 pos, 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of November 1993

Steve J. Herberg
Notary Public

My Commission Expires:



RECEIVED
NOV 29 1993

RECEIVED

well

CONTRACTOR'S WELL LOG

DEC 9 1980

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

TGT Petroleum Corporation
Abercrombie Drilling, Inc.
EINSEL "D" #1
C NW SW, Section 30-27S-18W
Kiowa County, Kansas
10/28/80
11/11/80

0	375	Surface Sand & Clay
375	1252	Redbeds and Shale
1252	4850	Lime & Shale
	4850	Rotary Total Depth

Spud hole at 3:00 p.m. 10/28/80. Drilled 375' of a 12 1/2" hole. Ran 8 jts. of 8 5/8" casing (tally 356.18') Set @ 366'. Cemented with 350 sx. of common, 2% gel, 3% c.c. Cement did circulate. Plug was down at 10:40 p.m. 10/28/80.

T.D. 4850'. Ran 127 jts. of 5 1/2" - 14# casing (tally 4879.87') Set @ 4851'. Cemented with 70 sx. of Halco Lite, 12# gilsinite per sx, followed with 200 sx. of 50/50 posmix, 10% salt. Job complete @ 2:00 p.m. 11/11/80.

SAMPLE TOPS:

Anhydrite 1196'
B/Anhydrite 1226'

STATE OF KANSAS,)
) SS
COUNTY OF SEDGWICK)


Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the EINSEL "D" #1, C NW SW, Section 30-27S-18W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
Jack L. Partridge, Asst. Sec./Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of December, 1980.

Jeanette A. Metheny
Jeanette A. Metheny, Notary Public



RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1993
CONSERVATION DIVISION
Wichita, Kansas