

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-10-81
NOV 10 1981
CONSERVATION DIVISION
Wichita Kansas

API Number 15-097-20,820,000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name F. L. F. Petroleum Corp.

Complete Address 209 East William St. Wichita, Kansas 67202

Lease Name Rice Well-No. A-2

Location C-5W-SW Sec. 31 Twp 27S Rge 18W (East)(West)

County Hiowa Total Depth 4890'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Co.

Address 801 Union Ctr. Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 11:00PM Day: 4 Month: November Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 432' of 8 5/8" surface casing cement circulated. The anhydrite was topped at 1178'. 1st plug 1100' with 70 lbs of cement. 2nd plug pushed rubber plug to 420' then pumped 40 lbs of cement on top of it. 3rd plug at 40' to 0' with 10 lbs of cement on solid bridge. They pumped 5 lbs of cement in rat hole + 5 lbs of cement in water well. Plugging was accomplished by Halliburton, Co. out of Pratt Kansas.

I hereby certify that the above plugging instructions were given as herein stated.

NOTICED
DATE 12-21-81
INV. NO. 8801-4

Signed: Paul Lutter
Conservation Division Agent

\$158.92