

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number ~~15-093-20,850~~
15-093-20,758

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Commonwealth Petroleum Co. Inc.

Complete Address 555 N. Woodlawn Suite 114 Wichita Kansas 67208

Lease Name Sturgen Well No. 1

Location C-NE-SW Sec. 35 Twp. 27 Rge. 18 (East)(West)

County Hiowa Total Depth 4880'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Lehen Drilling Co. Inc.

Address 210 Petroleum Bldg, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 10:30AM Day: 11 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1350'. 1st plug 1300' with 60 bbl of cement. 2nd plug pushed rubber plug to 280' with 35 bbl of cement pumped on top of it. 3rd plug at 40' to 0' with 10 bbl of cement on solid bridge. Then circulated 10 bbl of cement in rat hole & 5 bbl of cement in mouse hole & 3 bbl of cement in water well. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Dowell Cementing.

Amount of Surface Casing: 294' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
3-16-82
MAR 16 1982

Signed: _____
Conservation Division Agent
Wichita, Kansas

3-17-82
9680W