

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 04 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 -097-20264000 (of this well)

Operator's Full Name Patton Oil Co
Complete Address 5660 S Syracuse Circle Suite 200 Englewood, CO
Lease Name Fark Well No. A-1
Location C SE Sec. 35 Twp. 27 Rge. 18 (E) (W) X
County Kiowa Total Depth 4810
Abandoned Oil Well X Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Voth Casing Pulling Co
Address 715 So A Arkansas City, KS License No. 684
Operation Completed: Hour 11:00 AM Day 30 Month 9 Year 1976

The above well was plugged as follows:

321 ft 8 5/8 surface cemented with 250 sacks. 4807 ft 4 1/2 long string
cemented with 225 sacks. Bridge plug set at 4796 ft. Top perf. 4191
ft. Push plug, to 4100 ft. Sand, 4 sacks cement with bailer. Pulled
2640 ft 4 1/2. Set 10 ft rock bridge at 240 ft. Fill hole with 4 yards
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10-5-76

INV. NO. 3938-W