

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,715-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name HUMMON CORPORATION

Complete Address ONE MAIN PLACE, STE 400, WICHITA, KS 67202

Lease Name CECIL Well No. 1

Location C. SW. NW Sec. 2 Twp. 27 Rge. 17 (East)(West)

County KIOWA Total Depth 4720'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor CLARKE CORPORATION

Address 107 W. FOWLER, MEDICINE LODGE, KS 67101 License No. 5705

Operation Completed: Hour: 3:00pm Day: 21 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

4 1/2" P.S. @ 4665' w/125 sy - 2113' recovered - bottom sandbed to 4550 and 5 sy cement spotted on tag.

Ordered 150 sy of 50/50 Poz mix, 4% gel - 3% C.C. and pumped the following sequence: 2 sy hulls, 10 sy gel, 50 sy Cmt., 1 sy hulls, 10 sy gel and release 8 5/8" wood plug followed by 100 sy Cmt.

Cementing by Haliburton

Amount of Surface Casing: 8 5/8" s.p. @ 359' w/250 sy

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Barburton
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-8-82

W.P. # 1294-w