

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- - ✓

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720 Fourth Financial Center, Wichita, Kansas 67202

Lease Name Long Well No. 1-13

Location C of NW N¹/₄ Sec. 13 Twp. 27S Rge. 17W (East) (West)

County Kiowa Total Depth 4685'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour: 12:00 Noon Day: 4 Month: 9 Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

440' of 8 5/8" SP W/30A sks

4 1/2" csg. set @ 4684' W/225 sks

P.B. to 4635' Perfs 4594' to 4597'

Sand back to 4550' & 4 sks cement

Pump 15 gel 6 hulls & 10 sks gel, release plug and displace

W/150 sks 50/50 pozmix 4% gel 3% C.C.

Sun-Cementers SIP 400# Rec. 2410' 4 1/2" csg.

RECEIVED
STATE CORPORATION COMMISSION
9-9-81
SEP - 9 1981
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10/29/81

I hereby certify that the above well was plugged as herein stated.

INV. NO. 8133-W

Signed: M. T. Hester
Conservation Division Agent