


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 10 Twp. 27S Rge. 15W (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Osage Oil & Gas Company, Inc.
Lease Name Cochran Well No. 2
Office Address Petroleum Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-26 1956
Application for plugging filed 5-14 1958
Application for plugging approved 5-15 1958
Plugging commenced 5-15 1958
Plugging completed 5-15 1958
Reason for abandonment of well or producing formation Formation became dry

If a producing well is abandoned, date of last production 4-15 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp, Jr. Rt. 1, Stafford, Kans.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4715 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	301	none
				5 1/2"	4714	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 4398' dumped 5 sacks of cement. Pulled pipe to 1500' circulated 45 sacks of mud. Mud hole to 310' set rock bridge. Dumped 20 sacks of cement mud hole up to 35' set rock bridge dumped 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L. Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin

(Address) _____

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1958

My commission expires June 14, 1961

Phyllis Brown
Phyllis Brown Notary Public.

RECEIVED
MAY 20 1958
5-20-58
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 10 T. 27 R. 15W
BOOK PAGE 100 LINE 29

DRILLERS' LOG

Company: Osage Oil & Gas Company, Inc.

Farm Name: Cochran Well No. 2

Total Depth: 4715'

Comm: 11/2/56 Comp: 11/26/56
Contractor: Glenn W. Peel

Casing: 8 5/8" @ 301' cem.
5 1/2" @ 4714' cem.

SE NW SE
Sec. 10, Twp. 27S, Rg. 15W,

County: Pratt,
Kansas

Elevation:

Production:

Figures below indicate bottoms of formations:

Surface soil	0 -	130
Shale and sand		301
Shale		500
Shale and shells		1550
Red bed and shale		1820
Anhydrite		1850
Shale		1950
Shale and lime		2115
Lime		2240
Lime and shale		3945
Lime		4465
Lime and shale		4485
Lime		4635
Lime and shale		4680
Lime		4715
Total Depth		4715

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 27th day of November, 1956.

My commission expires: April 27, 1960

Ruth Brant
Notary Public

RECEIVED
NOTARY COMMISSION
MAY 20 1956

PLUGGING
FILE SEC. 10 T. 27 R. 15W
BOOK PAGE 100 LINE 29