

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt

County. Sec. 10 Twp. 27S Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE NW

Lease Owner Cooperative Refinery Association

Lease Name Cochran "C" Well No. 1

Office Address Box 765 Gt. Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 28 19 56

Application for plugging filed December 28 Verbal permission obtained 19 56

Application for plugging approved Verbal permission obtained 19

Plugging commenced December 27 19 56

Plugging completed December 28 19 56

Reason for abandonment of well or producing formation

Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 55 sacks cement from 4495 to 4251. Filled hole with rotary mud to 310'. Pumped plug to 300' and dumped 20 sacks cement inside of surface pipe. Filled hole with mud to 20' of surface. Pumped plug down to 20'. Dumped 7 sacks cement. Complete

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1956
12-29-56
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C.R.A. Company Rig #5
Address Box 765 Gt. Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. D. Sullivan

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. D. Sullivan
Box 765 Gt. Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of December, 19 56

My commission expires September 24, 1960

Yvonne Adams
Notary Public.

PLUGGING
FILE SEC. 10 T. 27 R. 15W
BOOK PAGE 129 LINE 32

DRILLERS LOG

Cochran "C" #1

Elevation: 2047 R.B.
Casing: 8 5/8" @ 253' w/ 300 sx.

Loc: C SE SE NW
Sec: 10-27S-15W
Pratt County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Company Rig #5

Comm: 12-4-56 Comp: 12-28-56
Total Depth: 4495'

From	To	Formation
0	90	Sand and clay
90	310	Shale and sand
310	345	Shale
345	945	Red bed, shale, shells
945	975	Anhydrite
975	1500	Shells and shale
1500	1750	Shells, shale, lime
1750	3725	Shale and lime
3725	3785	Lime
3785	3980	Lime and shale
3980	4265	Lime
4265	4411	Lime and shale
4411	4450	Shale, lime, chert
4450	4473	Lime, shale, sand
4473	4495	Lime, chert, shale
4495		R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1956
CONSERVATION DIVISION
Wichita, Kansas

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Cochran "C" #1 well, located C SE SE NW of Section 10-27S-15W, Pratt County, Kansas.

M. D. Sullivan

Subscribed and sworn to before me this 28 day of December 1956.

Yvonne Adams

My commission expires: September 24, 1960

PLUGGING
FILE SEC. 10 T. 27 R. 15W
BOOK PAGE 129 LINE 32