


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County. Sec. 27 Twp. 27SRge. 14W E/A  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
1980' FWL & 405' FSL  
Lease Owner Thomas E. Black d/b/a Black Petroleum Co.  
Lease Name Reed Well No. 1  
Office Address 545 W. W. Garvey Bldg., Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202  
Dry Hole  
Date Well completed November 24, 1979  
Application for plugging filed Verbal Application 1979  
Application for plugging approved Verbal Approval 1979  
Plugging commenced November 24, 1979  
Plugging completed November 24, 1979  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 1979

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,200'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	369'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,200 ft. (rotary total depth) to 370 ft. Set plug at 370 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 370 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1979  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
Box 963, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent (~~XXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)



SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 79

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Thomas E. Black d/b/a Black Petroleum Company

SEC. 27 T. 27S R. 14W  
LOC. 1980'FWL & 405'FSL

FARM Reed

NO. 1

COUNTY Pratt

ROTARY TOTAL DEPTH 4,200'

COMM. November 17, 1979 COMP. November 24, 1979

CONTRACTOR H-30, Inc. (Rig #3)

ISSUED November 30, 1979

CASING

10 3/4"  
8 5/8" Set at 369' cemented w/225 sxs cements  
5 1/2"  
4 1/2"

ELEVATION 1,949' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	130'
Red Bed and Shale	1,055'
Shale	2,083'
Shale and Lime	2,515'
Lime and Shale	2,740'
Shale and Lime	2,950'
Lime and Shale	3,355'
Shale and Lime	3,600'
Lime and Shale	4,200'
Rotary Total Depth	4,200'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 30th day of November, 1979.



My Commission Expires:  
July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION  
*Elsie Willison*  
Elsie Willison - Notary Public  
DEC - 3 1979

CONSERVATION DIVISION  
Wichita, Kansas