


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 5 Twp. 27 Rge. 14W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
E/2 NE NE

Lease Owner Petrie Enterprises, Inc.  
Lease Name Strobel #1 Well No. \_\_\_\_\_  
Office Address Pratt, Kansas 67124  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11/21/77 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 11/26/77 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted. \_\_\_\_\_

If a producing well is abandoned, date of last production  
\_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4475  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	347	none
				5 1/2"	4112	3292'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded to 3900' and ran 5 sacks cement. Shot pipe at 3805', 3650', 3525', 3400', 3270',  
pulled 104 joints. Squeezed hole with 3 sacks hulls, 25 sacks gel, released plug and  
displaced with 125 sacks 50/50 pozmix, 2% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.


(Signature) R. Darrell Kelso  
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 77

Margaret Melcher  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

My commission expires



NOV 30 1977

CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

STROBEL NO. 1

*Patrice Enterprises, Inc.*

CASING REPORT:  
8 5/8" set at 347'  
W/375 sacks cement

OPERATOR: Okar Energy, Inc.

DESCRIPTION:

CONTRACTOR: Search Drilling Company

E/2 NE NE,  
Sec. 5-27S-14W  
Pratt County,  
Kansas

TOTAL DEPTH:

COMMENCED: July 24, 1974

4475'

COMPLETED: August 4, 1974

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	95	
Sand and Red bed	95	919	
Shale, Clay, Shells	919	1445	
Shale	1445	1880	
Shale and Lime	1880	2070	
Shale	2070	2225	
Shale and Lime	2225	2258	
Shale and Lime	2258	2319	
Shale and Lime	2319	2528	
Shale and Lime	2528	2690	
Shale and Lime	2690	2850	
Lime and Shale	2850	3040	
Lime and Shale	3040	3180	
Lime and Shale	3180	3315	
Lime and Shale	3315	3447	
Lime	3447	3565	
Lime	3565	3707	
Lime and Shale	3707	3845	
Lime	3845	3950	
Lime	3950	3955	
Kansas City Lime	3955	4021	
Lime	4021	4052	
Lime	4052	4074	
Lime	4074	4113	
Lime	4113	4133	
Lime	4133	4189	
Lime	4189	4274	
Lime and Chert	4274	4280	
Lime and Shale	4280	4330	
Lime and Chert	4330	4395	
Lime	4395	4463	
Lime	4463	4475	

5 1/2" set at 4475'  
15 jts. used - 116  
jts. new K-55 -  
cemented w/125 sacks  
commom-10% Salt -  
preceded by 15 bbls.  
of salt flush

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

*William J. Froelich, Jr.*  
\_\_\_\_\_  
William J. Froelich, Jr.

Subscribed and sworn to before me this 6th. day of August, 1974.

My commission expires:  
February 19, 1974

*Maxine Dressen*  
\_\_\_\_\_  
Maxine Dressen Notary Public

