


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Pratt County. Sec. 5 Twp. 27S Rge. 14W E/4  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C-E/2 NE NW  
Lease Owner Kansas Oil Corporation  
Lease Name Southwestern College "A" Well No. 1  
Office Address 555 N. Woodlawn, Wichita, KS 67208  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed December 20, 1980  
Application for plugging filed Verbal Application 1980  
Application for plugging approved Verbal Approval 1980  
Plugging commenced December 20, 1980  
Plugging completed December 20, 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,175'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	319'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,175 ft. (rotary total depth) to 360 ft. Set plug at 360 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.  
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gary Younger, Agent (~~XXXXXX~~ of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Younger  
251 N. Water - Suite 10, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1981

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

STATE CORPORATION COMMISSION

1-23-81  
JAN 23 1981

CONSERVATION DIVISION  
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Kansas Oil Corporation

SEC. 5 T. 27S R. 14W

LOC. C-E/2 NE NW

FARM Southwestern College "A" No. 1

COUNTY Pratt

ROTARY TOTAL DEPTH 4,175'

COMM. December 11, 1980 COMP. December 20, 1980

CONTRACTOR H-30, INC. (Rig #2)

ISSUED January 12, 1981

CASING

10 3/4"

8 5/8" Set at 319' cemented w/375 sxs cement

ELEVATION 2,014' K.B.

5 1/2"


4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	360'
Sand	364'
Shale	700'
Sand and Shale	988'
Shale	1,912'
Shale and Lime	2,095'
Shale	3,005'
Lime and Shale	3,345'
Lime	3,514'
Lime and Shale	3,745'
Lime	4,175'
Rotary Total Depth	4,175'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

  
 Gary Younger

State of Kansas )  
 ) SS:  
 County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 12th day of January, 1981.

  
 Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982