

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20,067-0000

LEASE NAME Gibbons

WELL NUMBER 5

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 27 RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 5-13-97

Plugging Completed 5-15-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA Operating Co., Inc.

ADDRESS P. O. Box 159 Stafford, KS 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4384'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	182'	none
				5 1/2	4384'	3014'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s. Sanded bottom to 3738' & ran 5 sks cement. Shot at 3616', worked pipe. Shot at 3209', worked pipe. Shot at 3014', worked pipe free. Pulled up to 720', pumped 10 sks gel followed by 50 sks cement. Pulled up to 220', pumped 100 sks cement. Pulled rest of casing & topped w/25 sks. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMA Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac-
statements, and matters herein contained and the log of the above-described well as filed t
the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 97

Irene Herberg
Notary Public

My Commission Expires:



RECEIVED
MAY 22 1997
5-22-97