

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt

County. Sec. 36 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NW 1/4 NE 1/4 SW 1/4

Lease Owner The El Dorado Refining Company

Lease Name Gibbons Well No. 1

Office Address 1020 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-30 1956

Application for plugging filed 11-30 1956

Application for plugging approved 11-30 1956


Plugging commenced 11-30 1956

Plugging completed 11-30 1956

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4463 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	398'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled well with heavy mud to 300', set plug, put in 1/4 sack hulls and 20 sacks cement through drill pipe, filled to 35' with heavy mud, put in top plug and 1/4 sack hulls and run 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Lester Matthew (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lester Matthew

915 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of December, 1956

A. R. Derrington (A. R. Derrington) Notary Public.

My commission expires August 20, 1960

PLUGGING
FILE SEC. 36 T. 27 R. 13W
BOOK PAGE 121 LINE 26

RECEIVED
STATE CORPORATION COMMISSION
12-6-56
DEC 6 1956

WELL LOG

COMPANY The El Dorado Refining Company

SEC. 36 T. 27 R. 13-W
 LOC. NW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$


FARM Gibbons

NO. 1

Pratt

COUNTY

KANSAS



TOTAL DEPTH 4463'

DDMM. 11-15-56

COMP. 11-30-56

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

ELEVATION 1873 K.B.

PRODUCTION

CASING

20	10	
15	8	8-5/8" = 398'
12	6	
13	5	

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	40	Soil & Sand
40 -	160	Sand
160 -	395	Red Bed & Shells
395 -	715	Red Bed & Shale
715 -	740	Anhydrite
740 -	1225	Shale & Shells
1225 -	1275	Anhydrite
1275 -	1875	Shale & Shells
1875 -	2040	Lime
2040 -	2220	Lime & Shale
2220 -	2310	Shale & Shells
2310 -	2550	Lime & Shale
2550 -	2775	Shale & Shells
2775 -	3295	Shale & Lime
3295 -	3430	Lime
3430 -	3615	Lime & Shale
3615 -	3725	Shale
3725 -	3929	Lime
3929 -	3940	Kansas City Lime
3940 -	4217	Lime
4217 -	4265	Lime & Shale
4265 -	4280	Chert
4280 -	4316	Chert & Sand
4316 -	4346	Simpson Sand
4346 -	4418	Sand & Shale
4418 -	4463	Arbuckle Lime

GEOLOGIC TOPS:

Lansing	3752'
Base/Kansas City	4094'
Mississippi Chert	4190'
Kinderhook Shale	4219'
Viola	4235'
Simpson	4292'

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 6 - 1956
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of SEDGWICK } ss:

I, Lester Matthew of the Lewis Drilling Company
 upon oath state that the above and foregoing is a true and correct copy of the log of the Gibbons #1 well.

FILE NO. 36 T. 27 R. 13W
 PAGE 26

Lester Matthew
 (Lester Matthew)

Subscribed and sworn to before me this 4th day of December 19 56

My Commission Expires: August 20, 1960

A. R. Derrington
 NOTARY PUBLIC
 (A. R. Derrington)