

LEASE NAME H. Gibbons

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 35 TWP. 27S RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 10-6-93

Plugging Completed 10-25-93

LEASE OPERATOR RAMA Operating Co., Inc.

ADDRESS P. O. Box 159, Stafford, KS 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4385'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8	185'	none.
				5 1/2	4385'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Sanded bottom @ 4300' & 5 sks cement. Shot @ 3000', 2800', 2600' & 2400'. Pipe came loose. Pulled pipe. Plugged well down 13 3/8 casing with 300# C.S. Hulls, 1000# gel, 80 sks cement, 1000# gel, 200# C.S. Hulls, 175 sks cement. Close in well, 60/40 pos 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMA Operating Co., Inc.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso RECEIVED

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of November NOV 03 1993, 1993

James Dumberg CONSERVATION DIVISION
Notary Public Wichita, Kansas

My Commission Expires: _____



SCHLUMBERGER**SIDEWALL
NEUTRON POROSITY LOG**

COUNTY PRATT
 FIELD or ROLINGSON
 LOCATION SEC. 35-27S-13W
 WELL H. GIBBONS NO. 1
 WM. GRUENERWALD
 COMPANY AND ASSOCIATES

COMPANY WM. GRUENERWALD AND ASSOCIATESWELL H. GIBBONS NO. 1FIELD ROLINGSONCOUNTY PRATT STATE KANSASLocation: C-SE-SESec. 35 Twp. 27S Rge. 13W

Other Services:

DIL
 FDC-GR
 SYNERGETIC

Permanent Datum: GROUND LEVEL; Elev.: 1870
 Log Measured From K.B., 8 Ft. Above Perm. Datum
 Drilling Measured From K.B.

Elev.: K.B. 1878
D.F. ----
G.L. 1870

Date 11-1-68
 Run No. ONE
 Type Log SNP-GR
 Depth—Driller 4385
 Depth—Logger 4385
 Bottom logged interval 4384
 Top logged interval 3000
 Type fluid in hole SALT MUD
 Salinity, PPM Cl. 27,300 (R)
 Density 9.1
 Level FULL
 Max rec. temp., deg F. 111
 Operating rig time 2 1/2 HOURS
 Recorded by HALL
 Witnessed by WRIGHT

CONFIDENTIAL

STATE RECORD
 CASING RECORD
 CORPORATION COMMISSION
 11/6/91 - 1993

RUN No.	BORE-HOLE RECORD		To	Size	Wgt.	From	To
	Bit	From					
ONE	7 7/8	180	4385	13 3/8	---	---	---