

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pratt County, Sec. 35 Twp. 27 Rge. 13 (E) (W)
SE NW SE
Location as "NE/CNWxSWx" or footage from lines.
Lease Owner Crawford Drilg. & Expl., Inc.
Lease Name DeWayne Moore Well No. 2
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-30 1958
Application for plugging filed 7-8 1971
Application for plugging approved 7-8 1971
Plugging commenced 7/13/71 19
Plugging completed 7/16/71 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation SIMPSON Depth to top 4329 Bottom 4363 Total Depth of Well 4384' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8	196	none
				5 1/2"	4384'	3238'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked sand, loaded hole with water, set 5 sacks of cement.
Shot pipe at 3497', 3401', 3334', 3276', pulled 100 joints of 5 1/2" casing. Bailed hole to 160', set rock bridge and ran 5 yards of ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1971

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG

9P

COMPANY Clinton Oil Company

SEC. 35 T. 27S R. 13W

FARM Moore

NO. 2

LOC. NW SE


TOTAL DEPTH 4381'

COUNTY Pratt Co., Kansas

COMM. 12-16-68

COMP. 12-30-68

CONTRACTOR Garvey Drilling Company



CASING 13 3/8" @ 196' w/325 sx
5 1/2" @ 4380' w/150 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 133' Sand
- 530' Red Bed
- 575' Anhydrite
- 1790' Shale & Shells
- 2160' Lime & Shale
- 2355' Lime
- 3770' Lime & Shale
- 4170' Lime
- 4284' Chert & Lime
- 4381' Lime
- 4381' RTD

State of Kansas }
County of Barton }

I, Eunice McEachern of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Moore No. 2 well.

Eunice McEachern

Subscribed and sworn to before me this 4th day of January 1969

My Commission Expires: November 5th, 1969

Richard Hays
NOTARY PUBLIC