

KANSAS

24
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Richard Duffley Co.

Complete Address Box 5897 Great Bend Kansas

Lease Name M. H. Hunt G-3 Well No. 3-

Location SW-NE-SE Sec. 13 Twp. 27 Rge. 13 (E) W

County Pratt Total Depth 4362

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Bullis Inc.

Address Box 486 Ellsworth Kansas License No. 462

Operation Completed: Hour 6:30 P Day 9 Month 6 Year 68

The above well was plugged as follows:

430 ft of 8 3/4 in surface pipe circulated with cement
4362 ft of 5 1/2 in pipe sanded up to 4200 ft and 5 sacks of
cement, clogging at 400 ft a 10 ft rock bridge 25 sacks
of cement, and mud up to 40 ft, a 10 ft rock bridge
and 10 sacks of cement to surface.

Recovered 3029 ft of 5 1/2 in pipe

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 6/11/68
INV. NO. 7927-W