

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3
1-8-82
RECEIVED
STATE CORPORATION COMMISSION
4-20-82
APR 20 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-151-20

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Lewers Oil Company, Inc.

Complete Address 125 N. Market Ste. 1425 Wichita 67202

Lease Name Shogon Well No. 3

Location SW-501-5E Sec. 2 Twp. 22 Rge. 13 (East) (West)

County Pratt Total Depth 4348'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour: 2¹⁵ PM Day: 15 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

4 1/2" set c 4371' w/175' of PB to 4220'
Top Perf 3956' to 60' SB to 3900', dump 4' of
Dump 15 gel 6 bulls 10 gel, Release plug
& displace w/ 150 of Common 300 C.C.
Howell SEP-150#

Amount of Surface Casing: 923' of 8 5/8" Csg.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 4-27-82
INV. NO. 9975-W

Signed: _____
Conservation Division Agent

WELL LOG

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Sheegog #3
 LOCATION: Approx 100' N.E. of SW-SW-SE
 Section 2-27S-13W
 Pratt County, Kansas
 COMMENCED: July 21, 1969
 COMPLETED: August 3, 1969
 ELEVATION: 1908 Kelly Bushing
 1906 Derrick Floor
 1902 Ground Level

0 - 922	Redbed	
922 - 3822	Shale & Lime	Set 8 5/8" casing at 923' with 600 sacks cement.
3822 - 3895	Lime	
3895 - 3933	Lime & Shale	
3933 - 4183	Lime	
4183 - 4254	Lime & Chert	
4254 - 4380	Lime	Set 4 1/2" casing at 4371 with 175 sacks cement
4380	T. D.	

LOG TOPS:

Topeka	3196
Heebner	3544
Toronto	3558
Douglas	3583
Brown Lime	3705
Lansing	3733
Base/Kansas City	4053
Marmaton	4077
Mississippian	4159
Viola	4204
Simpson	4242
Simpson Dolomite	4253
Simpson Sand	4269
Arbuckle	4348

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the #3 Sheegog located approx. 100' Northeast of SW-SW-SE Section 2-27S-13W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, this 8th day of August, 1969.

Carole A. Young
 Carole A. Young, Notary Public

My commission expires May 12, 1973

RECEIVED
 STATE CORPORATION COMMISSION

APR - 9 1969

CONSERVATION DIVISION
 Wichita, Kansas